# SECTION 500

GUARDRAIL, MEDIAN BARRIER, FENCING & MARKERS

STANDARD					
	THIS PAGE INTENTIONALLY LEFT BLANK				
VOOT	TITI C				
ROAD AND BRIDGE STANDARDS  SHEET 1 OF 1 REVISION DATE	TITLE				
	VIRGINIA DEPARTMENT OF TRANSPORTATION				

STANDARD THREE BEAM GUARDRAN HARDWARE   500.0	STANDARD	TITLE			
STANDARD THREE BEAM CUARDRAL HARDWARE   501.0	GR-HDW	STANDARD W-BEAM GUARDRAIL HARDWARE			
GR-2, 2A         STANDARD BLOCKED-DUT W-BEAM GUARDRAL ISTRONG POST SYSTEMI POST AND BLOCKOUT DETALS         5010           GR-3         CABLE GUARDRAILS         5010           CABLE GUARDRAIL         5010           TERMINAL TREATMENT FOR W-BEAM GUARDRAIL         5010           GR-7         BREWKAY CABLE TERMINAL -4 FLARE         5011           BREWKAY CABLE TERMINAL -4 FLARE         5011           GOLTBERGER BREWAY -4 FLARE (SITE PREPARATION)         5011           GR-8, BA, BR, BC         STANDARD W-BEAM GUARDRAIL (MEAN POST SYSTEM)         5011           GR-9         ALTERNATE BREWAWAY CABLE TERMINAL - NO FLARE (SITE PREPARATION)         5011           GR-10         GUARDRAIL AT LOW FILL CULVERT         5011           GR-10         GUARDRAIL AT LOW FILL CULVERT         5011           GR-11         TRAILING BLOCK CULVERT GUARDRAIL (TEXAS TS)         5012           GR-10         STANDARD BOX CULVERT GUARDRAIL (TEXAS TS)         5012           GR-10 LI STANDARD BOX CULVERT GUARDRAIL (TEXAS TS)         5012           GR-10 LI STANDARD BOX CULVERT GUARDRAIL (TEXA		STANDARD W-BEAM GUARDRAIL HARDWARE	501.02		
STANDARD BLOCKED-OUT W BEAM GUARDRAIL (STRONG POST SYSTEM) POST AND BLOCKOUT DETAILS  CABLE QUARDRAILS  CABLE GUARDRAILS  CABLE CLARDRAILS  CREE CLARDRAILS  CREE CLARDRAILS  CREE CLARDRAILS  CREE CLARDRAILS  SOLO  GR-6  ITERMINAL TREATMENT FOR W-BEAM GUARDRAIL  SOLO  TERMINAL TREATMENT FOR W-BEAM GUARDRAIL  SOLO  GR-7  BREAKWAY CABLE TERMINAL -4 FLARE  SOLO  GR-8, BA, BB, BC  STANDARD GUARDRAIL (WEAR POST SYSTEM)  SOLO  GR-9  ALTERNITE BREAKWAY CABLE TERMINAL -NO FLARE (SITE PREPARATION)  GR-10  GUARDRAIL AL LOW-FLL COLEVERT  GR-10  GUARDRAIL AL LOW-FLL COLEVERT  SOLO  GR-11  TRAILING END TERMINAL TREATMENT  SOLO  STANDARD BOX COLEVERT QUARDRAIL (TEXAS TOL)  SOLO  GR-FOA-2  W BEAM QUARDRAIL-FRED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (STEEL POSTS)  SOLO  GR-FOA-2  W BEAM QUARDRAIL-FRED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (STEEL POSTS)  SOLO  GR-FOA-2  W BEAM QUARDRAIL-FRED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECT AND QUARDRAIL (STEEL POSTS)  SOLO  GR-FOA-2  W BEAM QUARDRAIL-FRED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECT AND QUARDRAIL (STEEL POSTS)  SOLO  GR-FOA-2  W BEAM QUARDRAIL INSTALLATION ORTERIA (STEEL OBJECT ATTACHMENT FOR USE BETWE		STANDARD THRIE BEAM GUARDRAIL HARDWARE	501.03		
GR-3         CABLE GUARDRAILS         501.0           CABLE GUARDRAILS         501.0           GR-6         TERMINAL TELATMENT FOR W-BEAM GUARDRAIL         501.0           GR-7         BREAKWAY CABLE TERMINAL - 4 FLARE         501.3           BREAKWAY CABLE TERMINAL - 4 FLARE         501.3           BREAKWAY CABLE TERMINAL - 4 FLARE (SITE PREPARATION)         501.7           GR-8, BA, BB, BC         STANDARD W-BEAM GUARDRAIL (NEAK POST SYSTEM)         501.7           GR-9, BA, BB, BC         STANDARD W-BEAM GUARDRAIL (NEAK POST SYSTEM)         501.7           GR-9         ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE         501.7           GR-10         GUARDRAIL AT LOW-FEL CULVERT         501.7           GR-10         GUARDRAIL AT LOW-FEL CULVERT         501.7           GR-11         TRAULING END TERMINAL TREATMENT         501.2           GR-11         TRAULING END TERMINAL TREATMENT         501.2           GR-11         TRAULING END TERMINAL TREATMENT         501.2           GR-12         STANDARD BOX CULVERT GUARDRAIL (TEXAS TE)         501.2           STANDARD BOX	GR-2, 2A	STANDARD BLOCKED-OUT W-BEAM GUARDRAIL (STRONG POST SYSTEM)	501.04		
CABLE GUARDRAILS		STANDARD BLOCKED-OUT W-BEAM GUARDRAIL (STRONG POST SYSTEM) POST AND BLOCKOUT DETAILS	501.05		
CABLE CHARDRAILS         \$9.00           CR-6         TERMINAL TREATMENT FOR WISEAM GUARDRAIL         \$9.00           CR-7         BREAWAY CABLE TERMINAL - 4*FLARE         \$9.01           BREAWAY CABLE TERMINAL - 4*FLARE         \$9.01           BREAWAY CABLE TERMINAL - 4*FLARE         \$9.01           GR 8, 8A, 8B, 8C         \$130,000 MEGAN GUARDRAIL (WEAK POST SYSTEM)         \$9.01           STANDARD WISEAM GUARDRAIL (WEAK POST SYSTEM)         \$9.01           STANDARD WISEAM GUARDRAIL (WEAK POST SYSTEM)         \$9.01           SR-9         ALTERNATE BREAKAWY CABLE TERMINAL - NO FLARE (SITE PREPARATION)         \$9.01           GR-10         GUARDRAIL AT LOW-FILL CULVERT         \$9.01           GR-10         GUARDRAIL AT LOW-FILL CULVERT         \$9.01           GR-11         TRAILING END TERMINAL TREATMENT         \$9.12           GR-01         STANDARD BOX CULVERT GUARDRAIL (TEXAS T6)         \$9.12           GR-03         STANDARD BOX CULVERT GUARDRAIL (TEXAS T6)         \$9.12           GR-60-11         WISEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)         \$9.12           GR-F0A-1         WISEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BUTTERS SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)         \$9.12           GR-F0A-2         WISEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE	GR-3	CABLE GUARDRAILS	501.06		
Ser-6   TERMINAL TREATMENT FOR W-BEAM GUARDRAIL   501.00		CABLE GUARDRAILS	501.07		
TERMINAL TREATMENT FOR W-BEAM GUARDRAIL   501.0		CABLE GUARDRAILS	501.08		
SR-7   BREAKWAY CABLE TERMINAL - 4 FLARE   501.11	GR-6		501.09		
BREAKWAY CABLE TERMINAL - 4 FLARE 501LE BREAKWAY CABLE TERMINAL - 4 FLARE (SITE PREPARATION)  SOLIT  GR-8, 8A, 8B, 8C STANDARD W-BEAM GUARDRAIL (WEAK POST SYSTEM)  STANDARD W-BEAM GUARDRAIL (WEAK POST SYSTEM)  ALTERNATE BREAKWAY CABLE TERMINAL - NO FLARE (SITE PREPARATION)  GR-9 ALTERNATE BREAKWAY CABLE TERMINAL - NO FLARE (SITE PREPARATION)  GR-10 GUARDRAIL AT LOW-FLL CULVERT  GR-10 GUARDRAIL AT LOW-FLL CULVERT  GR-11 TRAILING END TERMINAL TREATMENT  SOLIT  BBR-01 STANDARD BOX CULVERT GUARDRAIL (TEXAS T6)  SOLIZ  GR-F0A-1 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  SOLIZ  GR-F0A-2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BITWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  SOLIZ  GR-F0A-2, & 4 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  SOLIZ  GR-F0A-4 BLOCKED-OUT W-BEAM MEDIAN BARRER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  SOLIZ  GR-F0A-2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  SOLIZ  GR-F0A-2 BLOCKED-OUT W-BEAM MEDIAN BARRER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN BARTY AND MB-3  BLOCKED-OUT W-BEAM MEDIAN BARRER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  SOLIZ  FOA-CZ W-BEAM GUARDRAIL-INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA		TERMINAL TREATMENT FOR W-BEAM GUARDRAIL	501.10		
BREAKWAY CABLE TERMINAL - 4"FLARE (SITE PREPARATION)  OR-8, BA, BB, BC  STANDARD W-BEAM GUARDRAL (WEAK POST SYSTEM)  STANDARD W-BEAM GUARDRAL (WEAK POST SYSTEM)  OR-9  ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE (SITE PREPARATION)  OUARDRAL AT LOW-FILL CULVERT OUARDRAL AT LOW-FILL CULVERT  OUARDRAL AT LOW-FILL CULVERT  OUARDRAL AT LOW-FILL CULVERT  OUARDRAL AT LOW-FILL CULVERT  OUARDRAL AT LOW-FILL CULVERT  OUARDRAL AT LOW-FILL CULVERT  OUARDRAL ON THE STANDARD BOX CULVERT GUARDRAL (TEXAS TE)  STANDARD BOX CULVERT GUARDRAL	GR-7	BREAKWAY CABLE TERMINAL - 4'FLARE	501.11		
BREAKWAY CABLE TERMINAL - 4 * FLARE (SITE PREPARATION)   501.1		BREAKWAY CABLE TERMINAL - 4'FLARE	501.12		
STANDARD W-BEAM GUARDRAIL (WEAK POST SYSTEM)  ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE  ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE (SITE PREPARATION)  SOLIT  GUARDRAIL AT LOW-FILL CULVERT  GUARDRAIL AT LOW-FILL CULVERT  GUARDRAIL AT LOW-FILL CULVERT  SOLIT  GR-10  TRAILING END TERMINAL TREATMENT  SOLIZ  STANDARD BOX CULVERT GUARDRAIL (TEXAS T6)  SOLIZ  GR-FOA-1  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  SOLIZ  GR-FOA-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  SOLIZ  GR-FOA-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  SOLIZ  GR-FOA-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  SOLIZ  GR-FOA-4  BLOCKED-OUT W-BEAM MEDIAN BARRER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  SOLIZ  FOA-CZ  W-BEAM GUARDRAIL INSTALLATION CRITERIA  SOLIZ  SOL			501.13		
ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE 501.0  ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE (SITE PREPARATION) 501.0  GR-10 GUARDRAIL AT LOW-FILL CULVERT 501.0  GUARDRAIL AT LOW-FILL CULVERT 501.0  GR-11 TRAILING END TERMINAL TREATMENT 501.2  BGR-11 TRAILING END TERMINAL TREATMENT 501.2  BGR-01 STANDARD BOX CULVERT GUARDRAIL (TEXAS T6) 501.2  GR-F0A-1 W BEAM GUARDRAIL-FIXED DBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED DBJECTS AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED DBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED DBJECTS AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED DBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED DBJECTS AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED DBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED DBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED DBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2  GR-F0A-2 & 4 W BEAM GUARDRAIL-FIXED DBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS) 501.3  GR-F0A-4 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3 501.3  GR-FOA-6 W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED DBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  GR-FOA-7 W-BEAM GUARDRAIL INSTALLATION CRITERIA FIXED DBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3	GR-8, 8A, 8B, 8C	STANDARD W-BEAM GUARDRAIL (WEAK POST SYSTEM)	501.14		
ALTERNATE BREAKAWAY CABLE TERMINAL 'NO FLARE (SITE PREPARATION)  GUARDRAIL AT LOW-FILL CULVERT  GUARDRAIL AT LOW-FILL CULVERT  501.8  GR-10  GUARDRAIL AT LOW-FILL CULVERT  501.8  GR-11  TRAILING END TERMINAL TREATMENT  501.2  STANDARD BOX CULVERT GUARDRAIL (TEXAS T6)  501.2  GR-F0A-1  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (STEEL POSTS)  501.2  GR-F0A-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  501.2  GR-F0A-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  501.2  GR-F0A-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  501.2  GR-F0A-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  501.2  GR-F0A-4  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3		STANDARD W-BEAM GUARDRAIL (WEAK POST SYSTEM)	501.15		
ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE (SITE PREPARATION)  GUARDRAIL AT LOW-FILL CULVERT  GUARDRAIL AT LOW-FILL CULVERT  501.8  GR-10  TRAILING END TERMINAL TREATMENT  501.2  SGR-01  STANDARD BOX CULVERT GUARDRAIL (TEXAS T6)  SGR-01  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  SGR-F0A-1  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  SGR-F0A-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  SGR-F0A-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  SGR-F0A-2, § 4  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  SGR-F0A-2, § 4  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  SGR-F0A-2  SGR-F0A-4  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MAP-T AND MB-3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  SGR-FOA-2  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  SO1.3	GR-9	ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE	501.16		
GR-10 GUARDRAIL AT LOW-FILL CULVERT 501.8 GUARDRAIL AT LOW-FILL CULVERT 501.8 GR-11 TRAILING END TERMINAL TREATMENT 501.2 GR-01 STANDARD BOX CULVERT GUARDRAIL (TEXAS T6) 501.2 GR-F0A-1 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS) 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS) 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2 GR-F0A-2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2 GR-F0A-2, & 4 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS) 501.3 GR-F0A-4 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3 501.3 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FURBRAIL AND HARDWARE DETAILS GR-INS W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3		ALTERNATE BREAKAWAY CABLE TERMINAL - NO FLARE (SITE PREPARATION)	501.17		
GUARDRAIL AT LOW-FILL CULVERT 501.5  GR-11 TRAILING END TERMINAL TREATMENT 501.2  GR-01 STANDARD BOX CULVERT GUARDRAIL (TEXAS T6) 501.2  GR-F0A-1 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (STEEL POSTS) 501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS) 501.3  GR-F0A-2, & 4 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  GR-F0A-4 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3 501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3	GR-10	GUARDRAIL AT LOW-FILL CULVERT	501.18		
SR-11 TRALING END TERMINAL TREATMENT 501.2  STANDARD BOX CULVERT GUARDRAIL (TEXAS T6) 501.2  SR-FOA-1 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (STEEL POSTS) 501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS) 501.2  SR-FOA-2, & 4 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  SR-FOA-4 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3					
SGR-01 STANDARD BOX CULVERT GUARDRAIL (TEXAS 16) 501.2 WW BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS) 501.2 WW BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.2 WW BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2 WW BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS) 501.2 SCR-FOA-2, & 4 WW BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3 SCR-FOA-4 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3 501.3 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3	GR-11	TRAILING END TERMINAL TREATMENT	501.20		
STANDARD BOX CULVERT GUARDRAIL (TEXAS 16) 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS) 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (STEEL POSTS) 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS) 501.2 SR-FOA-2, & 4 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3 501.3 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3			501.22		
STANDARD BOX CULVERT GUARDRAIL (TEXAS T6)  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (WOOD POSTS)  STANDARD BOX GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (STEEL POSTS)  STANDARD BOX GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  STANDARD BOX GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  STANDARD BOX GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  STANDARD BOX GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  STANDARD BOX GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  STANDARD BOX GUARDRAIL INSTALLATION CRITERIA  STANDARD GUARDRAIL GIVEN GUARDRAIL GIVEN GUARDRAIL GET ATTACHMENT METHODS FOR CONSTRUCTION ZONES)		STANDARD BOX CULVERT GUARDRAIL (TEXAS T6)	501.23		
SR-FOA-1  W BEAM GUARDRAL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAL (WOOD POSTS)  501.2  W BEAM GUARDRAL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAL (STEEL POSTS)  501.2  W BEAM GUARDRAL-FIXED OBJECT ATTACHMENT RUBRAL AND HARDWARE DETAILS  SR-FOA-2  W BEAM GUARDRAL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAL (WOOD POSTS)  501.2  W BEAM GUARDRAL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAL (STEEL POSTS)  501.2  GR-FOA-2, & 4  W BEAM GUARDRAL-FIXED OBJECT ATTACHMENT RUBRAL AND HARDWARE DETAILS  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAL AND HARDWARE DETAILS  501.3  FOA-CZ  W-BEAM GUARDRAL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES)  501.3  W-BEAM GUARDRAL INSTALLATION CRITERIA  501.3  W-BEAM GUARDRAL INSTALLATION CRITERIA  501.3  W-BEAM GUARDRAL INSTALLATION CRITERIA  501.3  501.3					
W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE WITH VERTICAL FIXED OBJECTS AND GUARDRAIL (STEEL POSTS)  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  GR-FOA-2  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  DEAD GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  SOL2  GR-FOA-2, & 4  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  SOL3  GR-FOA-4  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  FOA-CZ  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES)  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3	GR-FOA-1				
W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  GR-FOA-2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS) 501.2 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS) 501.2 GR-FOA-2, & 4 W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3 GR-FOA-4 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3 501.3 BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3 FOA-CZ W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3					
W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (WOOD POSTS)  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  501.2  GR-FOA-2, & 4  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  GR-FOA-4  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  FOA-CZ  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES)  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3			501.27		
W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)  501.2  GR-FOA-2, & 4  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  GR-FOA-4  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3  501.3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  FOA-CZ  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES)  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3	GR-FOA-2				
GR-FOA-2, & 4  W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  GR-FOA-4  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  FOA-CZ  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES)  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3		W BEAM GUARDRAIL-FIXED OBJECT ATTACHMENT FOR USE BETWEEN SAFETY SHAPE AND AND GUARDRAIL (STEEL POSTS)			
BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT FOR USE BETWEEN MB-7 AND MB-3  BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS  501.3  FOA-CZ  W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES)  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3	GR-FOA-2. & 4				
BLOCKED-OUT W-BEAM MEDIAN BARRIER - FIXED OBJECT ATTACHMENT RUBRAIL AND HARDWARE DETAILS 501.3  FOA-CZ W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES) 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3					
W-BEAM GUARDRAIL INSTALLATION CRITERIA (FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES)  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3  W-BEAM GUARDRAIL INSTALLATION CRITERIA  501.3			501.32		
W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3					
W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3					
W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3 W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3					
W-BEAM GUARDRAIL INSTALLATION CRITERIA 501.3	ł				
INDEX OF SHEETS			<b>V</b> D□T		

SECTION 500-GUARDRAIL, BARRIER AND FENCE

VIRGINIA DEPARTMENT OF TRANSPORTATION

ROAD AND BRIDGE STANDARDS SHEET 1 OF 3

REVISION DATE

500.01

STANDARD	TITLE	PAGE		
GR-INS	W BEAM GUARDRAIL INSTALLATION CRITERIA			
	W BEAM GUARDRAIL INSTALLATION CRITERIA	501.39		
	W BEAM GUARDRAIL INSTALLATION CRITERIA	501.40		
	W BEAM GUARDRAIL AND MEDIAN BARRIER INSTALLATION CRITERIA	501.41		
MB-3	BLOCKED-OUT W BEAM MEDIAN BARRIER	502.01		
MB-5	STANDARD W BEAM MEDIAN BARRIER (WEAK POST SYSTEM)	502.02		
	STANDARD W BEAM MEDIAN BARRIER (WEAK POST SYSTEM)	502.03		
MB-7D, 7E, 7F	CONCRETE MEDIAN BARRIER	502.04		
MB-7D PC	PRECAST TRAFFIC BARRIER CONCRETE SERVICE	502.05		
	PRECAST TRAFFIC BARRIER CONCRETE SERVICE	502.06		
MB-8A	CONCRETE MEDIAN BARRIER TYPE I, II OR III	502.07		
	CONCRETE MEDIAN BARRIER TYPE I, II, OR III	502.08		
MB-9A	CAST IN PLACE CONCRETE MEDIAN BARRIER 12 FOOT TERMINAL SECTION.	502.09		
MB-9A, PC	PRECAST CONCRETE MEDIAN BARRIER 12 FOOT TERMINAL SECTION	502.10		
MB-10A	TRAFFIC BARRIER SERVICE CONCRETE PARAPET (SINGLE FACE) (FOR TEMPORARY INSTALLATION ON BRIDGE DECK EXTERIC	DR) 502.11		
	TRAFFIC BARRIER SERVICE CONCRETE PARAPET (SINGLE FACE) (FOR TEMPORARY INSTALLATION ON BRIDGE DECK EXTERIC	DR) 502.12		
MB-11A	TRAFFIC BARRIER SERVICE CONCRETE PARAPET (DOUBLE FACE) (FOR TEMPORARY INSTALLATION ON BRIDGE DECK EXTERI	IOR) 502.13		
	TRAFFIC BARRIER SERVICE CONCRETE PARAPET (DOUBLE FACE) (FOR TEMPORARY INSTALLATION ON BRIDGE DECK EXTERI	IOR) 502.14		
	TRAFFIC BARRIER SERVICE CONCRETE PARAPET (DOUBLE FACE) (FOR TEMPORARY INSTALLATION ON BRIDGE DECK EXTERI	IOR 502.15		
MB-12A, B, C	CONCRETE MEDIAN BARRIER (TALL WALL)	502.16		
	CONCRETE MEDIAN BARRIER (TALL WALL)	502.17		
MB-13	CONCRETE MEDIAN BARRIER TYPE I, II OR III	502.18		
	CONCRETE MEDIAN BARRIER TYPE I, II OR III	502.19		
MB-INS	BUTTING TRAFFIC BARRIER SERVICE TO SINGLE FACE PARAPET SERVICE	502.23		
	BUTTING TRAFFIC BARRIER SERVICE TO SINGLE FACE PARAPET SERVICE	502.24		
	STANDARD FENCE GENERAL NOTES	503.01		
FE-W1, W2	STANDARD FENCE WOVEN WIRE FABRIC	503.02		
FE-B	STANDARD FENCE BARBED WIRE	503.03		
FE-CL	STANDARD FENCE CHAIN LINK	503.04		
FE-G	STANDARD FENCE GATES	503.05		
FE-4	WATER GATES IN FENCE LINES			
FE-6	STANDARD METHOD OF FENCE AND HANDRAIL GROUNDING			
RM-1	STANDARD PLAN AND METHOD OF SETTING RIGHT-OF-WAY MONUMENTS			
RM-2	STANDARD PLAN AND METHOD OF SETTING RIGHT-OF-WAY MONUMENTS	504.02		

 $\mathbf{V}$ DU I

ROAD AND BRIDGE STANDARDS

SHEET 2 OF 3 500.02

REVISION DATE 07/16

## INDEX OF SHEETS SECTION 500-GUARDRAIL, BARRIER AND FENCE

VIRGINIA DEPARTMENT OF TRANSPORTATION

STANDARD	TITLE			
IA-1	IMPACT ATTENUATOR TYPE 1RE-DIRECTIVE PERMANENT INSTALLATION (TL-3 ≥ 40 MPH)	505.01		
	IMPACT ATTENUATOR TYPE 1RE-DIRECTIVE PERMANENT INSTALLATION (TL-3 ≥ 40 MPH)	505.02		
	IMPACT ATTENUATOR TYPE 1RE-DIRECTIVE PERMANENT INSTALLATION (TL-3 ≥ 40 MPH)	505.03		
A-2	IMPACT ATTENUATOR TYPE 1RE-DIRECTIVE PERMANENT INSTALLATION (TL-2 < 40 MPH)	505.04		
	IMPACT ATTENUATOR TYPE 1RE-DIRECTIVE PERMANENT INSTALLATION (TL-2 < 40 MPH)	505.05		
A-LM	IMPACT ATTENUATOR LOW MAINTENANCE TYPE 1 RE-DIRECTIVE PERMANENT INSTALLATION (TL-3 > 40 MPH)	505.10		
	IMPACT ATTENUATOR LOW MAINTENANCE TYPE 1 RE-DIRECTIVE PERMANENT INSTALLATION (TL-3 > 40 MPH)	505.11		
MGS-HDW	MGS STANDARD GUARDRAIL HARDWARE	506.01		
	MGS STANDARD GUARDRAIL HARDWARE W-BEAM GUARDRAIL HARDWARE	506.02		
	MGS STANDARD GUARDRAIL HARDWARE THRIE BEAM GUARDRAIL HARDWARE	506.03		
GR-MGS1, 1A	MIDWEST GUARDRAIL SYSTEM (STANDARD AND REDUCED POST SPACING)	506.04		
		506.05		
GR-MGS2	MIDWEST GUARDRAIL SYSTEM (TANGENT END TERMINAL)	506.06		
		506.07		
		506.08		
GR-MGS3	MIDWEST GUARDRAIL SYSTEM (TRAILING END ANCHORAGE)	506.09		
		506.10		
GR-MGS4	MIDWEST GUARDRAIL SYSTEM (TRANSITION FROM MGS 31" HEIGHT TO GR-2 27 3/4" HEIGHT)	506.11		
GR-MGS-INS	MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA	507.01		
	MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA	507.02		
	MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA	507.03		
	MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA	507.04		
	MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA	507.05		
GR-F0A-5	MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA (LEAVE-OUT FOR STANDARD GUARDRAIL POST INSTALLATION)	508.01		
	THRIE-BEAM - FIXED OBJECT ATTACHMENT (FOR USE WITH VERTICAL FACE TERMINAL WALLS AND MGS GUARDRAIL)	508.02		
TCB-1	TEMPORARY CONCRETE BARRIER (MASH FREESTANDING PRECAST PIN AND LOOP FOR TEMPORARY USE)	509.01		
	TEMPORARY CONCRETE BARRIER (MASH FREESTANDING PRECAST PIN AND LOOP FOR TEMPORARY USE)	509.02		
	TEMPORARY CONCRETE BARRIER (MASH FREESTANDING PRECAST PIN AND LOOP FOR TEMPORARY USE)	509.03		
	INDEX OF SHEETS	VDOT		

INDEX OF SHEETS
SECTION 500-GUARDRAIL, BARRIER AND FENCE

VIRGINIA DEPARTMENT OF TRANSPORTATION


ROAD AND BRIDGE STANDARDS

REVISION DATE 04/20


SHEET 3 OF 3

STANDARD					
	THIS PAGE INTENTIONALLY LEFT BLANK				
VOOT	TITI C				
ROAD AND BRIDGE STANDARDS  SHEET 1 OF 1 REVISION DATE	TITLE				
	VIRGINIA DEPARTMENT OF TRANSPORTATION				

GR-HDW




W BEAM
BACK - UP PLATE




OF TRAFFIC

DETAIL OF SPLICE JOINT



DETAIL OF STANDARD WASHER

7/6 - 1/32 " - 5/8 - 11 NC - 2



L= 1/4" FOR SPLICE BOLT-FULL LENGTH THREADS

L= 2" FOR SPLICE BOLT-FULL LENGTH THREADS ON NESTED W BEAMS.

L= 10" FOR STEEL POST BOLT-1/2" MIN. THREADS

L= 18" FOR WOOD AND CONCRETE POST BOLT-21/2" MIN. THREADS

L= 26" FOR MB WOOD OR CONCRETE POST-2" MIN. THREADS

NOTES:

ALL HARDWARE IS TO BE GALVANIZED IN ACCORDANCE WITH THE SPECIFICATIONS.

THE GUARDRAIL AND MEDIAN BARRIER COMPONENTS DEPICTED IN ARTBA TECHNICAL BULLETIN NUMBER 268B MAY BE SUBSTITUTED IF INTERCHANGEABLE WITH THE STANDARDS FOR GUARDRAIL (GR) OR MEDIAN BARRIER (MB) AND APPROVED BY THE ENGINEER.

DETAIL OF BUTTON HEAD BOLT AND RECESS NUT (GUARDRAIL BOLT)

SPECIFICATION REFERENCE

221
505

STANDARD GUARDRAIL HARDWARE

ROAD AND BRIDGE STANDARDS

REVISION DATE SHEET 1 OF 3


VIRGINIA DEPARTMENT OF TRANSPORTATION


STANDARD GUARDRAIL HARDWARE

ROAD AND BRIDGE STANDARDS


REVISION DATE SHEET 1 OF 3

501.01





#### \* 2734" MIN - 2834" MAX RAIL HEIGHT



GR-2

(6'-3" POST SPACING)

MAX DYNAMIC DEFLECTION = 3"

#### NOTES:

GUARDRAIL LOCATIONS SHOWN ON PLANS ARE APPROXIMATE ONLY AND CAN BE ADJUSTED DURING CONSTRUCTION IF AND AS DIRECTED BY THE ENGINEER.

FOR DETAILS OF POST AND BLOCKOUTS SEE SHEET NO. 501.05.

FOR DETAILS OF RAIL ELEMENT, RAIL SPLICE JOINT, AND ASSOCIATED HARDWARE SEE SHEET NOS. 501.01 AND 501.02.


RAIL ELEMENTS ARE FURNISHED SHOP CURVED FOR RADII BETWEEN 5 FEET AND 150 FEET.

ALL GUARDRAIL POSTS SHALL BE SET PLUMB. POST SHALL NOT BE SET WITH A VARIATION OF MORE THAN 1/8" PER FOOT FROM VERTICAL. W-BEAM, BLOCKOUTS, AND POSTS SHALL BE SET AND ALIGNED WITHOUT ALTERATION OR FORCE, AS PER SECTION 505 OF THE SPECIFICATIONS.

ALL GR-2 AND GR-2A RAIL SHALL BE MAINTAINED AT A HEIGHT OF 27  $^3\!\!\!/_4$  " MIN - 28  $^3\!\!\!/_4$  " MAX AS MEASURED PER STANDARD GR-INS.

ALL W-BEAM RAILS SHALL BE LAPPED IN THE DIRECTION OF VEHICULAR TRAVEL FOR THE FINISHED ROADWAY.

THE OPTIONAL GR-2A METHODS OF NESTING THE RAIL OR USE OF AN ADDITIONAL RAIL ON THE BACK OF THE POST FOR STANDARD GR-2A SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.



GR-2A

(3'-1)/2'' POST SPACING) MAX DYNAMIC DEFLECTION = 2'



\* OPTIONAL GR-2A METHOD USING NESTED RAIL



\* OPTIONAL GR-2A METHOD USING ADDITIONAL RAIL ON BACK OF POST

\* WHEN NESTED RAIL OR ADDITIONAL RAIL IS PLACED ON BACK OF POST FOR GR-2A THE POST SPACING WILL BE 6'-3".

FLARE RATES						
DESIGN SPEED	INS SHY		OND LINE			
MPH	SHY LINE LS	FLARE RATE	FLARE RATE			
70	9'	30:1	15:1	*		
60	8'	26:1	14:1	*		
50	6.5'	21:1	11:1	*		
40	5'	16:1	8:1	*		
30	4'	13:1	7:1	*		

\* SUGGESTED MAXIMUM FLARE RATE FOR SEMI-RIGID BARRIER SYSTEMS.

ROAD AND BRIDGE STANDARDS

SHEET 1 OF 2 REVISION DATE

08/14

501.04


A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.


# STANDARD BLOCKED-OUT W-BEAM GUARDRAIL (STRONG POST SYSTEM)


VIRGINIA DEPARTMENT OF TRANSPORTATION


SPECIFICATION REFERENCE


> 221 505














TERMINAL END


SEE NOTE 2

#### NOTES:

GUARDRAIL

- GUARDRAIL TERMINAL, STD. GR-7 SHALL BE FROM VDOT'S APPROVED PRODUCT'S LIST.
- ALL TERMINALS SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S INSTALLATION INSTRUCTIONS AND THE FOLLOWING VDOT REQUIREMENTS:
  - A. ALL STANDARD GR-7 TERMINALS SHALL BE INSTALLED WITH A 4 FT. OFFSET.
  - B. YELLOW 8" X 36" REFLECTIVE SHEETING, IN ACCORDANCE WITH VDOT SPECIFICATIONS, SHOULD BE APPLIED IN TERMINALS EMPLOYING W-BEAM END SECTIONS. FOR TERMINALS EMPLOYING IMPACT (EXTRUDER) HEADS, AMBER (YELLOW) REFLECTIVE SHEETING WITH BLACK DIAGONAL STRIPES SHOULD BE APPLIED TO THE FULL AREA INSIDE THE IMPACT HEAD WITH THE DIRECTION OF THE BLACK DIAGONAL STRIPES CONFORMING TO CURRENT MUTCD APPLICATION FOR TYPE 3 OBJECT MARKERS (OM-3).
  - C. DO NOT CHANGE THE LAPPING OF TERMINAL FOR ANY INSTALLATIONS. INSTALL AS SHOWN BELOW REGARDLESS OF ADJACENT TRAFFIC DIRECTION.
  - D. HEIGHT MEASURED AT TOP OF W-BEAM IS 273/1 MIN. 283/1 MAX.

- 3. IF THE NECESSARY CLEAR RUNOUT AREA FOR THE GR-7 TERMINAL CANNOT BE OBTAINED, CONSIDER ALTERNATIVE TERMINAL OPTIONS.
- THIS DRAWING IS REPRESENTATIONAL ONLY. DETAILS, DIMENSIONS, QUANTITIES, AND OTHER INFORMATION NOT SHOWN WILL VARY FOR EACH MANUFACTURER. SEE INDIVIDUAL MANUFACTURER'S PLANS FOR THIS INFORMATION.



37'-6" (TYP.)

	37 6 (TIL.)						
	B≪┐					A ≪┐	
<u> </u>		:: <del></del>			·		<del></del>
₹ 1:•:		:: <u> </u>	•	· :::]	: <u> ::</u>		\$\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
		1.1	1.1	1.1	1.1	1.1	1.1
9	® B <b>←</b>	6	5	4	3		1
	_			<u> </u>	<u> </u>	J	


**SPECIFICATION** A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE. REFERENCE FLARED END TERMINAL 221 (4' FLARE) 505 VIRGINIA DEPARTMENT OF TRANSPORTATION


ROAD AND BRIDGE STANDARDS REVISION DATE SHEET 1 OF 3


**\**VDOT


07/16


501.11


























GENERAL NOTE:

ALL STRUCTURAL STEEL, INCLUDING BOLTS, NUTS, AND WASHERS SHALL BE GALVANIZED.

FOR DETAILS OF GUARDRAIL, SEE GR-2 OF THE ROAD AND BRIDGE STANDARDS.

THE GUARDRAIL INSTALLATION SHALL CONFORM WITH SECTION 505 OF THE CURRENT VIRGINIA DEPARTMENT OF TRANSPORTATION ROAD AND BRIDGE SPECIFICATIONS.

RAIL POSTS MAY BE VERTICAL OR PERPENDICULAR TO ADJACENT ROADWAY GRADE AND CROSS SLOPE. TOP OF PEDESTAL SHALL BE SLOPED AS NECESSARY FOR PERPENDICULAR INSTALLATION.

DETAILS ON THIS SHEET ARE TO BE USED FOR BOTH STRAIGHT AND SKEWED BOXES.

ANCHOR BOLTS SHALL BE  $\frac{7}{8}$ "  $\emptyset$ A307 (OR A36 THREADED RODS WITH TACK WELDED NUTS) WITH HEX NUTS AND WASHERS AS SHOWN. THREADED RODS MAY BE 0.781 MIN, DIAMETER WITH ROLLED THREADS. NUTS SHALL CONFORM TO A307 REQUIREMENTS AND SHALL BE TAPPED OR CHASED AFTER GALVANIZING. BOLTS AND NUTS SHALL HAVE CLASS 2A AND 2B FIT TOLERANCES. BOLTS SHALL BE EMBEDDED 8" INTO THE CONCRETE.

THIS RAIL HAS BEEN SUCCESSFULLY EVALUATED BY FULL SCALE IMPACT TESTS CONDUCTED IN ACCORDANCE WITH NCHRP REPORT 153. TEST DOCUMENTATION MAY BE FOUND IN RESEARCH REPORT 230-1, "TUBULAR W-BEAM BRIDGE RAIL", OF RESEARCH STUDY 2-5-78-230 "BRIDGE RAIL TO CONTAIN HEAVY TRUCKS AND BUSES", TEXAS TRANSPORTATION INSTITUTE, OCTOBER 1978.

THIS UNIT IS ONLY TO BE USED WHEN DESIGN SPEED IS 45 MPH OR LESS.
TESTED - NCHRP 350 TEST LEVEL 2

TUBULAR GUARD RAIL SHALL BE FURNISHED AND INSTALLED IN 25 FT. SECTIONS. TUBULAR RAIL MEMBER SHALL BE EXTENDED AND CONNECTED TO AT LEAST THE FIRST SOIL EMBEDDED POST AT EACH END OF THE STRUCTURE. MORE SUCH POSTS SHALL BE USED TO UTILIZE 25 FT. STANDARD SECTIONS. APPROACH GUARDRAIL POSTS SHALL BE SPACED AT 6'-3" ADJACENT TO THE TUBULAR RAIL SINCE ITS FLEXIBILITY IS SIMILAR TO THE STANDARD METAL BEAM GUARDRAIL. DO NOT INSTALL ADDITIONAL POSTS AT 3'-11/2" CENTERS. FULLY ANCHORED GUARDRAIL MUST BE ATTACHED AT BOTH ENDS OF TUBULAR RAIL.

TESTS HAVE SHOWN THAT ALTHOUGH THIS RAIL DEFLECTS HORIZONTALLY TWO OR THREE FEET, ADEQUATE VEHICLE CONTAINMENT AND RE-DIRECTION IS ACHIEVED. THE RESULTING MORE GRADUAL DECELERATION THUS PRODUCES A SAFER CONDITION THAN AFFORDED BY OTHER BRIDGE RAILINGS.

THE CONTRACTOR SHALL DETERMINE THE NUMBER OF PEDESTALS REQUIRED FOR GUARDRAIL INSTALLATION ACROSS THE BOX, PEDESTAL HEIGHT AND DIMENSIONS OF THE BR SERIES REINFORCING BARS. THE QUANTITY OF CONCRETE (CLASS A4) AND REINFORCING STEEL USED IN THE PEDESTALS SHALL BE FIELD VERIFIED AND PAID FOR AT THE UNIT PRICE BID FOR THE CORRESPONDING BOX QUANTITIES. THE RAILING (TEXAS T-6) SHALL BE MEASURED IN 25 FT. SECTIONS AND PAID FOR AT THE CONTRACT UNIT PRICE PER LINEAR FOOT IN ACCORDANCE WITH SECTION 410 OF THE SPECIFICATIONS. BR SERIES BARS SHALL BE #5 IN SIZE.

FOR DETAILS OF BOX CULVERTS, SEE THE BOX CULVERT STANDARDS.

THIS SHEET IS APPLICABLE WHEN GUARDRAIL IS REQUIRED AND THE DEPTH OF FILL ABOVE THE TOP SLAB OF THE BOX CULVERT IS LESS THAN 3'-7".

DETAILS SHOWN ARE FOR INSTALLATION ON NEW BOX CULVERTS. INSTALLATION OF PEDESTALS ON EXISTING BOX CULVERTS SHALL BE IN ACCORDANCE WITH SEC. 412 OF THE SPECIFICATIONS EXCEPT THAT DOWELS SHALL BE PLACED BETWEEN 3 AND 6 INCHES FROM THE EDGE OF THE PEDESTAL.

PRECAST BOXES SHALL BE TREATED AS AN EXISTING BOX FOR PEDESTAL INSTALLATION.

ROAD AND BRIDGE STANDARDS

SHEET 1 OF 3 REVISION DATE


501.22


STANDARD BOX CULVERT GUARDRAIL
(TEXAS T-6)

VIRGINIA DEPARTMENT OF TRANSPORTATION

SPECIFICATION REFERENCE

STRUCTURE AND BRIDGE DIVISION








NOTES:

TUBULAR W-BEAM RAIL MEMBER IS TO BE FABRICATED FROM STANDARD 25'NOMINAL W-BEAM SECTIONS. TOP AND BOTTOM SEAMS SHALL BE BUTT WELDED 6" AT 12" SPACING. CONTINUOUS SEAM WELDING IS ALSO ACCEPTABLE. WELDS SHALL BE CHIPPED AND CLEANED AND THE COMPLETE 25 FT. TUBULAR MEMBER SHALL BE GALVANIZED AFTER FABRICATION. FOR TUBULAR RAIL SPLICE ADDITIONAL POST MOUNTING SLOTS ARE TO BE MADE IN EACH MEMBER 1'-3" FROM THE STANDARD SLOTS AT 6'-3" CENTERS.

8-5%" SPLICE NUTS SHALL BE TACK WELDED TO A BENT SHEET METAL POSITIONER AS SHOWN. OTHER SUITABLE POSITIONING METHODS OR OR DEVICES MAY BE SUBSTITUTED. THE COMPLETED SPLICE SHALL HAVE B BOLTS (16 BOLTS IF A TUBULAR RAIL SPLICE). EACH BOLT WILL INCLUDE A 13/4"X 3"X3/6" PLATE WASHER OR A 2 INCH DIAMETER WASHER.







ROAD AND BRIDGE STANDARDS

SHEET 3 OF 3 REVISION DATE

501.24


### STANDARD BOX CULVERT GUARDRAIL


(TEXAS T-6)


VIRGINIA DEPARTMENT OF TRANSPORTATION


SPECIFICATION REFERENCE

STRUCTURE AND BRIDGE DIVISION













GR-FOA-2










2016 ROAD & BRIDGE STANDARDS FOA-CZ **SPLICE** 2'-0" ς SPLICE 4 SPACES CONSTRUCTION 4 SPACES @ 3'-11/2" ST'D. GUARDRAIL STANDARD @ 1'-63/4' WORK ZONE GUARDRAIL VARIABLE SEE NOTE 4 1'-0" MAX. VARIABLE TWO SECTIONS W-BEAM SEE NOTE 3 TRAFFICE BARRIER SERVICE ONE NESTED INSIDE THE OTHER STANDARD W-BEAM TERMINAL CONNECTOR 1. HOLES, WHERE SHOWN, SHALL BE FORMED WITH SLEEVES OF 11/2" RUN OFF DIAMETER NOMINAL PIPE. RUN ON (ONE WAY TRAFFIC TYPE II) 2. BOLT LENGTHS ARE TO BE ESTABLISHED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. ALL BOLTS ARE TO BE  $\frac{7}{8}$ " DIA. HEX HEAD MACHINE BOLTS WITH BEVELED WASHERS AND SELF-(TYPE I) LOCKING NUTS. 3. FOR TWO-WAY TRAFFIC DESIGN, USE RUN-ON END TRANSITION (TYPE I). 4. RUN OFF (TYPE II) GUARDRAIL TO BE USED ONLY WHEN REQUIRED FOR OTHER REASONS. 5. COST OF TRANSITION TO BE INCLUDED IN PRICE BID PER FOOT OF TRAFFIC BARRIER SERVICE CONCRETE. 6. THESE INSTRUCTIONS APPLICABLE FOR TEMPORARY INSTALLATION IN CONSTRUCTION ZONES ONLY. REFER TO STANDARD GR-FOA FOR INSTRUCTIONS ON PERMANENT INSTALLATION. SAFETY-SHAPE BRIDGE PARAPET OR CONCRETE BARRIER SERVICE SEE NOTE 1 MAX 27¾" MIN. 28¾" **FINISHED** GRADE SECTION D-D RUN ON END TRANSITION **SPECIFICATION \**VDOT W-BEAM GUARDRAIL INSTALLATION CRITERIA REFERENCE ROAD AND BRIDGE STANDARDS


FIXED OBJECT ATTACHMENT METHODS FOR CONSTRUCTION ZONES


VIRGINIA DEPARTMENT OF TRANSPORTATION

REVISION DATE 7/11

SHEET 1 OF 1 501.33







NOTES:

GUARDRAIL INSTALLATION CRITERIA AS SHOWN ON THESE SHEETS IS TO APPLY TO THOSE LOCATIONS WHERE GUARDRAIL HAS TO BE TRANSITIONED FROM THE NORMAL LOCATION.


LENGTH OF TRANSITION (L) IS TO BE IN ACCORDANCE WITH TABLE III OR IV FOR APPLICABLE VALUES OF W OR AS DIRECTED BY THE ENGINEER.

RAIL TERMINAL SECTIONS IN ACCORDANCE WITH STANDARD GR-6, GR-7 OR GR-8 ARE TO BE INSTALLED AT EACH TERMINUS OF GUARDRAIL WHERE SPECIFIED ON PLANS.

ALL LENGTHS (L) ARE APPLIED ALONG FACE OF GUARDRAIL.

OFFSETS SHOWN IN TABLES ARE FOR 6'-3" SPACING. FOR 12'-6" SPACING (GR-8) USE EVERY SECOND VALUE FOR Y.

INSTALLATION METHODS SHOWN ON THESE SHEETS ARE APPLICABLE TO STANDARD PLANS GR-2, GR-2A AND GR-8.



									T.	<b>ABLE</b>	: III										
				Ol	FFSE	TS	(Y) F	OR	INTR	RODU	CED	GUA	RDR.	AIL 1	TRAN	SITIO	ONS				
LENGTH L		x																			
IN FEET	IN	FEET	W-2'	W-3'	W-4'	W-5'	W=6'	W-7'	W-8'	W-9'	W-10'			W-13'	W-14'	W-15'	W-16'	W-17'	W-18'	W-19'	W-20'
	X1_	6.25	0.06	0.05	0.03	0.02	0.02	0.01	0.01	0.02	0.02	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.03		
	X2	12.50	0.22	0.19	0.11	0.08	0.06	0.05	0.06	0.06	0.07	0.08	0.08	0.09	0.10	0.10	0.11	0.12	0.13	0.13	0.14
37.50	X3	18.75	0.50	0.42	0.25	0.18	0.14	0.11	0.12	0.14	0.16	0.17	0.19	0.20	0.22	0.23	0.25	0.27	0.28		
	X4	25.00	0.89	0.75	0.44	0.31	0.24	0.19	0.22	0.25	0.28	0.31	0.33	0.36	0.39	0.42	0.44	0.47	0.50		
	X5	31.25	1.39	1.17	0.69	0.49	0.38	0.30			0.43	0.48		0.56	0.61	0.65	0.69	0.74	0.78	0.82	0.87
	X6	37.50	2.00	1.69	1.00	0.70	0.54	0.44	0.50		0.62	0.69	0.75	0.81	0.87	0.94	1.00	1.06	1.13	1.19	1.25
50.00	X7	43.75		2.30	1.36	0.96	0.74	0.60		0.77	0.85	0.94	1.02	1.11	1.19	1.28	1.36	1.45	1.53		1.70
30.00	Х8	50.00		3.00	1.78	1.25	0.96	0.78		1.00	1.11	1.22	1.33	1.44	1.56	1.67	1.78	1.89	2.00	2.11	2.22
	Х9	56.25			2.25	1.58	1.22	0.98	1.12	1.27	1.41	1.55	1.69	1.83	1.97	2.11	2.25	2.39	2.53	2.67	2.81
75.00	X10	62.50			2.78	1.95	1.50	1.22	1.39	1.56	1.74	1.91	2.08	2.26	2.43	2.60	2.78	2.95	3.13	3.30	
	X <sub>11</sub>	68.75			3.36	2.36	1.82	1.47	1.68		2.10	2.31	2.52	2.73	2.94	3.15	3.36	3.57	3.78	3.99	4.20
	X12	75.00			4.00	2.81	2.16	1.75			2.50	2.75	3.00	3.25	3.50	3.75	4.00	4.25	4.50	4.75	
87.50	X <sub>13</sub>	82.25				3.30	2.54	2.05	2.35	2.64	2.93	3.23	3.52	3.81	4.11	4.40	4.69	4.99	5.28	5.57	5.87
07.00	X14	87.50				3.83	2.94	2.38	2.72	3.06	3.40	3.74	4.08	4.42	4.76	5.10	5.44	5.78	6.13	6.47	6.81
100.00	X15	93.75				4.39	3.38	2.73	3.12	3.52	3.91	4.30	4.69	5.08	5.47	5.86	6.25	6.64	7.03	7.42	
100.00	X16	100.00				5.00	3.84	3.11	3.56	4.00	4.44	4.89	5.33	5.78	6.22	6.67	7.11	7.56	8.00	8.44	8.89
	X <sub>17</sub>	106.25					4.33	3.51	4.01	4.52	5.02	5.52	6.02	6.52	7.02	7.53	8.03	8.53	9.03		10.03
125.00	X18	112.50					4.86	3.94	4.50	5.06	5.62	6.19	6.75	7.31	7.87	8.44	9.00	9.56	10.13	10.69	11.25
123.00	X <sub>19</sub>	118.75					5.41	4.39	5.01	5.64	6.27	6.89	7.52	8.15	8.77	9.40	10.03	10.65	11.28	11.91	12.53
	X20	125.00					6.00	4.86	5.56	6.25	6.94	7.64	8.33	9.03	9.72	10.42	11.11	11.81	12.50		13.89
	X21	131.25						5.36	6.12	6.89	7.66	8.42	9.19	9.95	10.72	11.48	12.25	13.02	13.78		15.31
150.00	X22	137.50						5.88	6.72	7.56	8.40	9.24	10.08	10.92	11.76	12.60	13.44	14.28	15.13	15.97	16.81
130.00	X23	143.75						6.43	7.35	8.27	9.18	10.10	11.02	11.94	12.86	13.78	14.69	15.61	16.53	17.45	18.37
	X24	150.00					_	7.00	8.00	9.00	10.00	11.00	12.00	13.00	14.00	15.00	16.00	17.00	18.00	19.00	20.00

SPECIFICATION REFERENCE

221

505

# W-BEAM GUARDRAIL INSTALLATION CRITERIA

VIRGINIA DEPARTMENT OF TRANSPORTATION


**W**DOT

ROAD AND BRIDGE STANDARDS

REVISION DATE

SHEET 4 OF 8

501.37



NOTE: GUARDRAIL INSTALLATION CRITERIA AS SHOWN ON THESE SHEETS IS TO APPLY TO THOSE LOCATIONS WHERE GUARDRAIL HAS TO BE TRANSITIONED FROM THE NORMAL LOCATION.

LENGTH OF TRANSITION (L) IS TO BE IN ACCORDANCE WITH TABLE III OR IV FOR APPLICABLE VALUES OF W OR AS DIRECTED BY THE ENGINEER.

RAIL TERMINAL SECTIONS IN ACCORDANCE WITH STANDARD GR-6, GR-7 OR GR-8 ARE TO BE INSTALLED AT EACH TERMINUS OF GUARDRAIL WHERE SPECIFIED ON PLANS.

ALL LENGTHS (L) ARE APPLIED ALONG FACE OF GUARDRAIL.

OFFSETS SHOWN IN TABLES ARE FOR 6'-3" SPACING, FOR 12'-6" SPACING (GR-8) USE EVERY SECOND VALUE OF Y.

INSTALLATION METHODS SHOWN ON THESE SHEETS ARE APPLICABLE TO STANDARD PLANS GR-2, GR-2A AND GR-8.

# TABLE IV OFFSETS (Y) FOR CONTINUOUS RUN-ON GUARDRAILS AND ALL RUN-OFF TRANSITIONS

			W-	2'	W-	٠3'	W-	٠4'	W-	·5'	w.	·6'	w-	·7'	w-	·8'	W-	9'	W-	10'	W-	·11'	W-	·12'
LENGTH L IN FEET	IN	X FEET	RUN ON	RUN OFF	RUN ON	RUN OFF	RUN ON	RUN OFF	RUN ON	RUN OFF	RUN ON	RUN OFF	RUN ON	RUN OFF	RUN ON	RUN OFF								
	X <sub>1</sub>	6.25	0.04	0.04	0.02	0.02	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.01	0.00	0.01	0.00	0.01	0.00	0.01	0.00	0.01	0.00	0.01
	X2	12.50	0.30	0.30	0.19	0.19	0.03	0.03	0.02	0.04	0.01	0.05	0.01	0.05	0.01	0.06	0.01	0.07	0.01	0.08	0.01	0.09	0.01	0.09
37.50	Х3	18.75	1.00	1.00	0.63	0.63	0.11	0.11	0.07	0.13	0.05	0.16	0.03	0.18	0.03	0.21	0.03	0.24	0.03	0.26	0.04	0.29	0.04	0.32
37.50	X <sub>4</sub>	25.00	1.70	1.70	1.50	1.50	0.25	0.25	0.16	0.31	0.11	0.38	0.08	0.44	0.06	0.50	0.07	0.56	0.08	0.63	0.09	0.69	0.09	0.75
	X5	31.25	1.96	1.96	2.37	2.37	0.49	0.49	0.31	0.61	0.22	0.73	0.16	0.85	0.12	0.98	0.14	1.10	0.15	1.22	0.17	1.34	0.18	1.46
	Х6	37.50	2.00	2.00	2.81	2.81	0.84	0.84	0.54	1.05	0.38	1.27	0.28	1.48	0.21	1.69	0.24	1.90	0.26	2.11	0.29	2.32	0.32	2.53
50.00	X7	43.75			2.98	2.98	1.34	1.34	0.86	1.67	0.60	2.01	0.44	2.34	0.33	2.68	0.38	3.01	0.42	3.35	0.46	3.68	0.50	4.02
55.55	Х8	50.00			3.00	3.00	2.00	2.00	1.28	2.50	0.89	3.00	0.65	3.50	0.50	4.00	0.56	4.50	0.63	5.00	0.69	5.50	0.75	6.00
	Xg	56.25					2.66	2.66	1.82	3.33	1.27	3.99	0.93	4.66	0.71	5.32	0.80	5.99	0.89	6.65	0.98	7.32	1.07	7.98
	X10	62.50					3.16	3.16	2.50	3.95	1.74	4.73	1.28	5.52	0.98	6.31	1.10	7.10	1.22	7.89	1.34	8.68	1.46	9.47
	X11	68.75					3.51	3.51	3.18	4.39	2.31	5.27	1.70	6.15	1.30	7.02	1.46	7.90	1.62	8.78	1.79	9.66	1.95	10.54
100.00	X12	75.00					3.75	3.75	3.72	4.69	3.00	5.63	2.20	6.56	1.69	7.50	1.90	8.44	2.11	9.38	2.32	10.31	2.53	11.25
	X13	81.25					3.89	3.89	4.14	4.87	3.69	5.84	2.80	6.82	2.15	7.79	2.41	8.76	2.68	9.74	2.95	10.71	3.22	11.68
	X14	87.50					3.97	3.97	4.46	4.96	4.26	5.95	3.50	6.95	2.68	7.94	3.01	8.93	3.35	9.92	3.68	10.91	4.02	11.91
	X <sub>15</sub>	93.75					4.00	4.00	4.69	5.00	4.73	5.99	4.20	6.99	3.30	7.99	3.71	8.99	4.12	9.99	4.53	10.99	4.94	11.99
	X <sub>16</sub>	100.00					4.00	4.00	4.84	5.00	5.11	6.00	4.80	7.00	4.00	8.00	4.50	9.00	5.00	10.00	5.50	11.00	6.00	12.00
	X17	106.25							4.93		5.40		5.30		4.70		5.29		5.88		6.47		7.06	
125.00	X18	112.50							4.98		5.63		5.72		5.32		5.99		6.65		7.32		7.98	
.20.00	X <sub>19</sub>	118.75							5.00		5.78		6.07		5.85		6.59		7.32		8.05		8.78	
	X20	125.00							5.00		5.89		6.35		6.31		7.10		7.89		8.68		9.47	
	X21	131.25									5.95		6.56 6.72		6.70		7.54		8.38		9.21 9.66		10.05	
150.00	X22	137.50									5.99		6.72		7.02 7.29		7.90 8.20		8.78		10.02		10.54	
	X23	143.75 150.00									6.00		6.92		7.50		8.44		9.11 9.38		10.02		11.25	
	X24	156.25									6.00		6.92		7.67				9.58		10.54		11.50	
	X25	162.50											6.99		7.79		8.62		9.74		10.54		11.68	
175.00	X26	168.75											7.00		7.79		8.76		9.85		10.83		11.82	
	X27	175.00													7.94		8.86		9.03		10.83		11.91	
	X28	181.25											7.00		7.94		8.93	-	9.92	-	10.91		11.91	
	X29	187.50													7.99		8.97 8.99		9.97	-	10.96		11.98	
200.00	X30	193.75													8.00			-	10.00		11.00		12.00	
	X31	200.00															9.00	-	10.00		11.00		12.00	
	X32	200.00													8.00		9.00		10.00		11.00		12.00	

ROAD AND BRIDGE STANDARDS

SHEET 5 OF 8 REVISION DATE

501.38


# W-BEAM GUARDRAIL INSTALLATION CRITERIA

HISTALLATION SINTLINA

SPECIFICATION REFERENCE

221 505

VIRGINIA DEPARTMENT OF TRANSPORTATION



ASPHALT CURB SECTION

GR-INS

27¾"MIN 28¾"MAX


-APPROACH

PAVED SHOULDER


# FACE OF GUARDRAIL IS TO BE ALIGNED WITH FACE OF CURB DESIGN SPEED > 45 MPH USE GR-2A 27¾"MIN 28¾"MAX DESIGN SPEED < 45 MPH USE GR-2 27¾"MIN 28¾"MAX TRAVEL LANE OR SHOULDER

# GR-2 INSTALLATION WITH CG-3 OR CG-7 CURB

FOR GUARDRAIL DESIGN POLICIES USING CURB & GUTTER OR URBAN DESIGNS WITH SIDEWALK OR SIDEWALK SPACE SEE APPENDIX I OF THE ROAD DESIGN MANUAL



GUARDRAIL LOCATION ON RECOVERABLE SLOPE



NOTE: PAVED SHOULDER WIDTHS SHOWN ARE MINIMUM.
THE PAVED SHOULDER MAY BE EXTENDED TO THE
FACE OF THE RAIL. THE PAVED WIDTH USED SHALL
BE IN ACCORDANCE WITH THE ROADWAY
CLASSIFICATION AS DEFINED IN THE ROAD DESIGN

SEE STANDARD MC-4 FOR PAVING UNDER GUARDRAIL

# TABLE I

NORMAL GUARDRAIL LOCATION-THROUGH TRAFFIC LANES LEFT OF TRAFFIC

		01 11(741110
TOTAL SHOULDER WIDTH (S) (PAVED & GRADED)	PAVED SHOULDER WIDTH (PS) (SEE NOTE)	OFFSET FROM EDGE OF TRAVELED WAY TO FACE OF GUARDRAIL (0)
17'	12'	14'
15'	3', 4', or 10'	12'
13'	3', 4', or 8'	10'
11'	3' or 4'	8'
9'	3' or 4'	6'
8'	3' or 4'	5'
7'	0 or 2'	4'
5'	0	2'

### TABLE II NORMAL GUARDRAIL LOCATION-THROUGH

TRAFFIC LANES RIGHT OF TRAFFIC

TOTAL SHOULDER WIDTH (S) (PAVED & GRADED)	WIDTH (PS)	OFFSET FROM EDGE OF TRAVELED WAY TO FACE OF GUARDRAIL (O)
17'	12'	14'
15'	6' or 10'	12'
13'	8'	10'
11'	3', 4' or 6'	8'
9'	0, 3', or 4'	6'
8'	0 or 3'	5'
7'	0 or 2'	4'
5'	0	2'

### NORMAL GUARDRAIL LOCATION

**SPECIFICATION** REFERENCE 221 505


A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.


GUARDRAIL INSTALLATION CRITERIA W-BEAM


VIRGINIA DEPARTMENT OF TRANSPORTATION

	$\mathbf{V}$ DOT								
ROAD	AND	BRID	GE	STAN	DAR	≀DS			
					_				

SHEET 6 OF 8 REVISION DATE 07/15 501.39







### NOTES:

STANDARD MB-3 POST SPACING IS 6'-3".

FOR DETAILS OF RAIL ELEMENT, RAIL SPLICE JOINT, W BEAM BACK UP PLATE, AND ASSOCIATED HARDWARE SEE SHEET NO. 501.01.


ALTERNATE TYPE POSTS AND BLOCKOUTS MAY BE INTERCHANGED ON ANY ONE PROJECT WITH THE RESTRICTION THAT THE SAME TYPE OF POST AND BLOCKOUT MUST BE USED IN ANY SINGLE RUN OF MEDIAN BARRIER.

ALL BOLTS, NUTS, WASHERS, STEEL POSTS, BENT PLATE POST, AND BLOCKOUTS ARE TO BE GALVANIZED.

\* STANDARD GR-11 TO BE USED ON RUN OFF END ONLY.

FLARE RATES						
DESIGN SPEED		IDE LINE	BE Y SHY	OND		
MPH	SHY LINE LS	FLARE RATE		ARE ATE		
70	9'	30:1	15:1	*		
60	8'	26:1	14:1	*		
50	6.5'	21:1	11:1	*		
40	5'	16:1	8:1	*		
30	4'	13:1	7:1	*		
. 0005						

\* SUGGESTED MAXIMUM FLARE RATE FOR SEMI-RIGID BARRIER SYSTEMS.



### METHOD OF TREATMENT AT BRIDGE PIER OR MEDIAN OBSTRUCTION

ROAD AND BRIDGE STANDARDS

SHEET 1 OF 1 REVISION DATE


502.01 07/16


A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.


BLOCKED-OUT W-BEAM MEDIAN BARRIER


VIRGINIA DEPARTMENT OF TRANSPORTATION

SPECIFICATION REFERENCE









#6 BAR

### NOTES:

- AT THE OPTION OF THE MANUFACTURER, ADDITIONAL REINFORCING MAY BE ADDED TO THE PRECAST CONCRETE BARRIER FOR HANDLING.
- CONCRETE SHALL BE 4000 P.S.I. MINIMUM.
- BARRIER DELINEATOR SIZE, COLOR AND SPACING SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS.
- COST OF DELINEATOR SHALL BE INCLUDED IN THE PRICE BID FOR TRAFFIC BARRIER SERVICE.
- OTHER PRECAST TRAFFIC BARRIER SERVICE CONCRETE DESIGNS THAT HAVE BEEN APPROVED BY VDOT AS AN ACCEPTABLE ALTERNATE TO THE STANDARD DESIGN MAY BE SUBSTITUTED.
- A 1" RADIUS MAY BE USED AS AN ALTERNATE FOR THE 3/4" CHAMFER.
- BARRIER DELINEATOR REFLECTIVE SURFACE IN ALL INSTANCES SHALL BE FACING ONCOMING TRAFFIC.
- BARRIER VERTICAL PANELS SHALL BE SPACED IN ACCORDANCE WITH VIRGINIA WORK AREA PROTECTION MANUAL.

WHEN USING VDOT STANDARD MB-7D PC WITH THE PIN AND LOOP POSITIVE CONNECTION, ALLOW FOR A 6'-0" DYNAMIC DEFLECTION. PROVIDE MIN. 60' OF BARRIER UPSTREAM AND DOWNSTREAM OF WORK ZONE FOR ANCHORAGE.
FOR APPROVED NON-VDOT DESIGNS, REFER TO MANUFACTURER'S INSTALLATION INSTRUCTIONS FOR DEFLECTIONS AND ANCHORAGE.

* FLARE RATES							
DESIGN SPEED	INSIDE LIN		BEYOND SHY LINE				
MPH	SHY LINE LS	FLARE RATE	FLARE RATE				
70	10'	30:1	20:1				
60	8	26:1	18:1				
50	6.5'	21:1	14:1				
40	5'	16:1	10:1				
30	3.5	13:1	8:1				

\* SUGGESTED MAXIMUM FLARED RATE FOR RIGID BARRIER SYSTEMS.

**\**VDOT ROAD AND BRIDGE STANDARDS SHEET 1 OF 2 REVISION DATE 03/17 502.05

END VIEW

PRECAST TRAFFIC BARRIER SERVICE CONCRETE (FOR TEMPORARY USE )


─ KEYWAY


SECTION A-A

VIRGINIA DEPARTMENT OF TRANSPORTATION

**SPECIFICATION** REFERENCE

MB-7D PC NOTES: PIN AND CONNECTORS SHALL BE ASTM-A36. REINFORCING STEEL BARS SHALL BE ASTM A 615 GRADE 60. ONE CONNECTOR PIN ASSEMBLY WITH EACH BARRIER SECTION. 1/3 DIA. -WASHER NUT-TOP | CONNECTOR ======= TOP CONNECTOR 6 Bar THREADS BURRED AFTER ASSEMBLY OF 1/3 DIA. BAR BOTTOM CÓNNECTOR - NUT 1/4" HEAVY HEX NUT WASHER 1/3 DIA. (4" TACK WELD NUT WHEN THREADED PLAN OF CONNECTION ROD IS USED **ELEVATION OF CONNECTION** 11/4" DIA. STEEL Bar (ASTM A36) 2 13/8"X21/2" STEEL WASHERS 1'-8" CONNECTOR PIN 21/2" **ASSEMBLY** GALVANIZE AFTER FABRICATION -0.165" THICK ·¾" Ø STEEL BAR -¾" Ø STEEL BAR **BOTTOM CONNECTOR** PLAIN GALVANIZED TOP CONNECTOR GALVANIZE AFTER FORMING STEEL WASHER FOR 1 1/4" PIN NOTE: ENTIRE CONNECTOR MAY BE GALVANIZED. **SPECIFICATION \**VDOT REFERENCE PRECAST TRAFFIC BARRIER SERVICE CONCRETE ROAD AND BRIDGE STANDARDS 105 (FOR TEMPORARY USE) REVISION DATE SHEET 2 OF 2 512 VIRGINIA DEPARTMENT OF TRANSPORTATION 7/16 502.06





TYPE III (GREATER THAN 2'-0" HT. DIFF., MAX. 3'-0")

# MEASUREMENT AND PAYMENT

MEDIAN BARRIER MB-8A TYPE I, II OR III WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER LIN. FOOT, WHICH SHALL BE FULL COMPENSATION FOR FURNISHING AND INSTALLING CLASS A3 CONCRETE, REINFORCING STEEL, POROUS BACKFILL AND ALL TOOLS, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK.
ANY ADDITIONAL EXCAVATION, BACKFILL WITH SUITABLE MATERIAL AND COMPACTION WORK NECESSARY FOR THE CONCRETE MEDIAN BARRIER INSTALLATION IS TO BE CONSIDERED INCIDENTAL IN THE BUILD RID FOR THE CONCRET CONSIDERED INCIDENTAL IN THE PRICE BID FOR THE CONCRETE MEDIAN BARRIER.

NOTE:

MB-8A

REINFORCING STEEL BARS SHOWN ARE BASED ON A 20' PANEL LENGTH.


ALL REINFORCING BARS ARE TO BE SIZE #4 GRADE 60 STEEL WITH A MINIMUM  $1/\!\!/_2$  CONCRETE COVER.

THE TYPICAL JOINT SPACING FOR CONSTRUCTION JOINTS IS 20' AND 80' FOR EXPANSION JOINTS FOR TYPE II AND III BARRIERS.

FOR DETAILS OF HOW JOINTS ARE TO BE FORMED & WATER STOP DETAILS SEE ST'D. RW-3.

TRANSVERSE JOINTS FOR TYPE I BARRIERS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ROAD AND BRIDGE SPECIFICATIONS EXCEPT NO SCORING OR SAWING WILL BE ALLOWED.

HORIZONTAL REINFORCING STEEL BARS B ARE TO BE SEPARATED AT ALL EXPANSION & CONTRACTION JOINTS. A 2" CONCRETE COVER IS REQUIRED OVER THE ENDS OF REINFORCING STEEL.




**X MB-7D BARRIER FACE** 


\*\* DENOTES FINISHED GRADE ELEVATION


A FOUNDATION MATERIAL UNDER MEDIAN BARRIER IS TO BE COMPACTED


			WIF AC	ILU.				
REINFORCING STEEL SCHEDULE								
	В	ARS "A"	B/	ARS A-1	ВА	RS "B"	DC	OWELS
PANEL	NO. LENGTH		NO.	LENGTH	NO.	LENGTH	NO.	LENGTH
TYPE I					2	19'-8"		
TYPE II	20	4'-0"	20	4'-0"	9	19'-8''	40	1'-0"
TYPE III	20	4'-0"	20	4'-0"	9	19'-8"	40	1'-0"


SPECIFICATION REFERENCE	CONCRETE MEDIAN BARRIER	ROAD AND BRID	DET DGE STANDARDS
105 404	TYPE I, II OR III	REVISION DATE	SHEET 2 OF 2
502	VIRGINIA DEPARTMENT OF TRANSPORTATION		502.08




















TEMPORARY INSTALLATION ON ASPHALT CONCRETE PAVEMENT, COMPACTED BASE MATERIAL, CONCRETE PAVEMENT, OR ASPHALT OVER CONCRETE PAVEMENT (NOT TO BE USED ON BRIDGE DECKS)

SECTION B-B

### NOTES:

- 1. STAKING OF STANDARD MB-11A TO ASPHALT CONCRETE PAVEMENT, COMPACTED BASE MATERIAL, CONCRETE PAVEMENT, OR ASPHALT OVER CONCRETE PAVEMENT IS REQUIRED WHEN TRAFFIC BARRIER SERVICE CONCRETE IS PLACED WITHIN THE TWO (2) FOOT OFFSET OF A TRENCHING OPERATION (4'OR GREATER IN DEPTH) OR WHEN DETERMINED BY THE ENGINEER.
- 2" MIN. FOR ASPHALT CONCRETE.
   6" MIN. FOR COMPACTED BASE MATERIAL.
- DRIVE STAKE HEAD BELOW FACE OF BARRIER TO PREVENT SNAGGING.
- 4. CONTRACTOR TO VERIFY PAVEMENT STRUCTURE PRIOR TO PLACING STAKES.
- 5. UPON REMOVAL OF THE STAKES AND BARRIERS, REPAIR THE RESULTING HOLES AS FOLLOWS OR AS DIRECTED BY THE ENGINEER. CLEAN AND FILL WITH TYPE EP-4 OR EP-5 EPOXY MORTAR CONFORMING TO THE REQUIREMENTS OF SECTION 243 OF THE SPECIFICATIONS FOR HYDRAULIC CEMENT CONCRETE PAVEMENT AND ASPHALT CONCRETE PAVEMENT. CARE SHALL BE TAKEN NOT TO TRAP AIR WITHIN OR AT THE BOTTOM OF THE EPOXY MORTAR.

ROAD AND BRIDGE STANDARDS

SHEET 3 OF 3 REVISION DATE


502.15 01/09

TRAFFIC BARRIER SERVICE CONCRETE PARAPET (DOUBLE FACE)


(FOR TEMPORARY INSTALLATION ON ROADWAYS)
VIRGINIA DEPARTMENT OF TRANSPORTATION

SPECIFICATION REFERENCE






### TRANSITION FROM 50" TALL WALL TO 32" JERSEY OR F-SHAPE BARRIER





IF BARRIER EXTENSION IS CONSTRUCTED AS A SEPARATE ITEM, ALL JOINTS ARE TO BE CONSTRUCTED AT THE SAME INTERVAL AS CONCRETE BARRIER. ALL VERTICAL BARS ARE #4 AT 24" MAX. SPACING. LENGTH OF DOWELS SHALL BE 20". VERTICAL BARS MAY BE PLACED IN THE CONCRETE OR BONDED INTO DRILLED HOLES IN HARDENED CONCRETE. WHEN HOLES ARE DRILLED NON-SHRINK GROUT SHALL BE USED TO BOND THE BARS IN PLACE.


▲ DEPTH OF CONCRETE BASE MAY BE EXTENDED AT THE CONTRACTOR'S OPTION TO COINCIDE WITH BOTTOM OF PAVEMENT COURSE IN WHICH BASE TERMINATES; HOWEVER, THE COST OF ADDITIONAL CONCRETE SHALL BE INCLUDED IN UNIT PRICE BID PER LINEAR FT. OF BARRIER.

SPECIFICATION REFERENCE	CONCRETE MEDIAN BARRIER (TALL WALL)	ROAD AND BRID	DE STANDARDS
105 502		REVISION DATE	SHEET 1 OF 2
502	VIRGINIA DEPARTMENT OF TRANSPORTATION		502.16















### NOTES:

- 1. BASIS OF PAYMENT:
  TRAFFIC BARRIER SERVICE LATERAL SUPPORT
  WILL BE MEASURED AND PAID FOR IN UNITS OF
  EACH COMPLETE IN PLACE AND SHALL INCLUDE
  FURNISHING AND PLACING PRECAST
  CONCRETE BARRIERS (TBS CONCRETE) AND SAND
  BAGS, MAINTENANCE, REMOVAL WHEN NO LONGER
  NECESSARY, AND ALL MATERIALS, LABOR, TOOLS,
  EQUIPMENTS, AND INCIDENTALS NECESSARY TO
  COMPLETE THE WORK.
- FOR POSITIVE CONNECTION DETAILS AND DIMENSIONS SEE STANDARD MB-7D PC.
- FOR DIMENSIONS NOT SHOWN, REFER TO ST'D. MB-7D PC AND MB-10A.



SPECIFICATION REFERENCE

BUTTING TRAFFIC BARRIER SERVICE

TO SINGLE FACE PARAPET SERVICE

VIRGINIA DEPARTMENT OF TRANSPORTATION

**\**VDOT

ROAD AND BRIDGE STANDARDS

REVISION DATE 03/17

SHEET 2 OF 2 502.24

STANDARD		
	THIS PAGE INTENTIONALLY LEFT BLANK	
	<b>T</b>	_
ROAD AND BRIDGE STANDARDS	TITLE	SPECIFICATION REFERENCE
SHEET 1 OF 1 REVISION DATE		
<u> </u>	VIRGINIA DEPARTMENT OF TRANSPORTATION	

### GENERAL NOTES - FENCING

## FARM FENCE

#### BARBED WIRE

BARBED WIRE IS TO CONFORM TO ONE OF THE TYPES ALLOWED BY THE SPECIFICATIONS.

UNLESS OTHERWISE NOTED ON PLANS FOUR STRANDS WILL BE PROVIDED.

SPACING OF STRANDS SHOWN IS SUGGESTED ONLY. ANY OTHER SPACING APPROVED BY THE ENGINEER MAY BE USED.

#### WOOD POSTS

WOOD POSTS TO BE SQUARE CUT OR ROUND TO THE DIMENSIONS SHOWN ON THE DRAWINGS.

POSTS TOPS MAY BE FLAT OR CUT AT A 30° ANGLE.

FOR WOVEN WIRE FABRIC, STAPLES ARE TO BE USED AT TOP AND BOTTOM STRANDS AND AT A MINIMUM OF THREE INTERMEDIATE STRANDS PER POST.

ONE STAPLE PER STRAND IS TO BE USED FOR BARBED WIRE FENCE.

WHERE GATE, CORNER, OR BRACE POSTS FALL IN ROCK OR MARSHY AREAS THEY SHALL BE SET IN CLASS A3 OR C1 CONCRETE.

### METAL POSTS

METAL POSTS ARE TO BE ONE OF THE TYPES SHOWN ON THE STANDARD DRAWINGS AND CONFORMING TO THE SPECIFICATIONS.

AT EACH CORNER AND STRETCHER POST WIRE FABRIC IS TO BE CUT AND ALL HORIZONTAL STRANDS SECURELY WRAPPED AROUND POST.

BRACES ON CORNER, STRETCHER AND END POSTS ARE TO BE SECURED 1'-6" FROM TOP OF POST WITH  $\frac{1}{2}$ " BOLTS.

IN LIEU OF SETTING POSTS IN CONCRETE, MANUFACTURER'S ANCHORING DEVICES MEETING THE SPECIFICATION REQUIREMENTS MAY BE USED WHEN APPROVED BY THE ENGINEER.

### **BRACES**

MAXIMUM SPACING BETWEEN BRACES TO BE 500'.

CORNER BRACES TO BE PROVIDED WHERE CORNER ANGLE IS 15° OR OVER.

LINE BRACES TO BE PROVIDED WHERE VERTICAL ALIGNMENT CHANGES 15° OR MORE AND WHERE SPACING REACHES 500'.

#### MISCELLANEOUS

FENCE IS TO BE LOCATED AS SHOWN ON THE PLANS OR DIRECTED BY THE ENGINEER.

THE SIDE OF THE POST TO WHICH FABRIC IS TO BE ATTACHED WILL BE DETERMINED BY THE ENGINEER.

FENCE TO BE GROUNDED IN ACCORDANCE WITH DETAIL SHOWN ON STANDARD FE-6 WHERE REQUIRED.

UNLESS SPECIFIED ON PLANS, THE CONTRACTOR WILL HAVE THE OPTION OF FURNISHING EITHER METAL OR WOOD POSTS. POSTS TYPES ARE NOT TO BE INTERMIXED ON ANY ONE INSTALLATION.

### CHAIN LINK FENCE

WIRE FABRIC

WIRE FABRIC SHALL HAVE A 2" MESH.

#### MISCELLANEOUS

IN LIEU OF SETTING POSTS IN CONCRETE, MANUFACTURER'S ANCHORING DEVICES MEETING THE SPECIFICATION REQUIREMENTS MAY BE USED WHEN APPROVED BY THE ENGINEER.

FOR GATES EXCEEDING 6'-0" IN WIDTH ROLLED FORMED STEEL POST WILL NOT BE ALLOWED.

CHAIN LINK FENCE TO BE GROUNDED IN ACCORDANCE WITH DETAILS SHOWN ON STANDARD FE-6, WHERE REQUIRED.

SPECIFICATION REFERENCE	STANDARD FENCE
	91711751175
	GENERAL NOTES
	VIRGINIA DEPARTMENT OF TRANSPORTATION


**W**DOT


ROAD AND BRIDGE STANDARDS


REVISION DATE


SHEET 1 OF 1

503.01









TI'X6" BRACES
BOTH SIDES

AND BRACES SEE
APPROPRIATE FENCE
STANDARD.


VAR.3',10',12',14',16'.

GATE POST

FOR DETAILS OF FENCE
AND BRACES SEE
APPROPRIATE FENCE
STANDARD.

FOR DETAILS OF FENCE
AND BRACES
AND BR

\* IF GATE WIDTH EXCEEDS 12', GATE POST IS TO BE SET 3'-6" INTO GROUND HEIGHT OF GATE POST ABOVE GROUND DEPENDS ON TYPE OF FENCE USED-5'-0", WOVEN WIRE FABRIC, 4'-6", BARBED WIRE.



WOOD GATE - WOOD POSTS - BARBED WIRE

WOOD GATE

BRACES ARE TO BE BOLTED AT EXTREMITIES AND INTERSECTIONS WITH A MIN. OF (2) 5/8" DIA. GALV. BOLTS, NUTS, AND WASHERS. ALL OTHER POINTS OF CONTACT ARE TO BE NAILED FROM BOTH SIDES WITH A MIN. OF 3-10D GALV. NAILS.

LUMBER FOR GATE IS TO BE ANY DRESSED, TRUE TYPE MEETING THE APPROVAL OF THE ENGINEER IT IS TO BE TREATED WITH PRESERVATIVES OTHER THAN CREOSOTE.

WOOD GATE IS TO HAVE TO COATS OF EXTERIOR WHITE PAINT UNLESS OTHERWISE DIRECTED BY THE ENGINEER. PAINT IS TO MEET THE REQUIREMENTS OF THE CURRENT ROAD AND BRIDGE SPECIFICATIONS.

METAL GATE

GATE FRAME AND CENTER BRACE TO BE TO THE DIMENSIONS SHOWN ON THE DRAWING EXCEPT THAT A 3" WIDTH GATE CAN HAVE A MIN. 1" FRAME WITH NO CENTER BRACE.

GATE IS TO BE HOT DIPPED GALVANIZED OR ELECTROPLATE GALVANIZED IN ACCORDANCE WITH ASTM A-164 TYPE GS.

GATE FABRIC IS TO BE ALL #11 GAUGE EXCEPT TOP AND BOTTOM STRANDS WHICH ARE TO BE #9 VERTICAL STRANDS ARE TO BE SPACED 6" APART.

MISCELLANEOUS


<u>IF LOCATIONS</u> OF GATES ARE NOT SPECIFIED ON PLANS, THEY ARE TO BE ERECTED AT THE SITES DESIGNATED BY THE ENGINEER.

GATE HINGE AND LATCH ASSEMBLIES MAY BE OF ANY TYPE MEETING THE APPROVAL OF THE ENGINEER, EXCEPT THAT ALL HINGES ARE TO BE OF A BOLT-THROUGH TYPE. ALL FITTINGS ARE TO BE HOT DIPPED GALVANIZED.

ANY COMBINATION OF GATE AND FENCE TYPES MEETING THE APPROVAL OF THE ENGINEER WILL BE ACCEPTABLE AND IS NOT LIMITED TO THE EXAMPLES SHOWN HEREON.

WHERE WOOD GATES POSTS FALL IN ROCK OR MARSHY AREAS THEY ARE TO BE SET IN CLASS A3 OR C1 CONCRETE.






SUGGESTED HINGE ASSEMBLY


### SPECIFICATION REFERENCE 242 507 236


# STANDARD FENCE GATES


VIRGINIA DEPARTMENT OF TRANSPORTATION

<b>V</b> DOT		
ROAD AND BRIDGE STANDARDS		
REVISION DATE	SHEET 1 OF 1	
	503.05	









STANDARD		
	THIS PAGE INTENTIONALLY LEFT BLANK	
	<b>T</b>	_
ROAD AND BRIDGE STANDARDS	TITLE	SPECIFICATION REFERENCE
SHEET 1 OF 1 REVISION DATE		
<u> </u>	VIRGINIA DEPARTMENT OF TRANSPORTATION	

NOTES IA-1

- DESIGN SHOWN IS REPRESENTATIONAL ONLY, SEE MANUFACTURER'S DRAWINGS FOR COMPONENTS AND INSTALLATION INSTRUCTIONS.
- 2. IMPACT ATTENUATOR SHALL BE SELECTED FROM VDOT'S PROVISIONALLY APPROVED MASH LIST, ALL UNITS MUST HAVE SUCCESSFULLY PASSED THE MASH 2016 TL-3 TESTING CRITERIA AND DEEMED REIMBURSABLE BY FHWA.
- 3. ALL STEEL HARDWARE COMPONENTS SHALL BE GALVANIZED.
- 4. IMPACT ATTENUATOR MANUFACTURER MUST FURNISH DETAILS FOR REQUIRED ANCHORING SYSTEM. FOR DIMENSIONS OF UNIT AND CONCRETE FOUNDATION SEE MANUFACTURER'S DRAWINGS AND SPECIFICATIONS.
- 5. CROSS SLOPE OF THE PAD SHALL NOT EXCEED A 8% (12:1) SLOPE.
- 6. ANY LOCATION WHERE THERE IS REVERSE DIRECTION TRAFFIC, A TRANSITION PANEL SHALL BE SUPPLIED BY THE MANUFACTURER AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S DRAWINGS AND SPECIFICATIONS.
- 7. DUE TO THE VARYING LENGTHS OF PROPRIETARY IMPACT ATTENUATORS THE DESIGNER SHOULD ALLOW 30' FOR THE LENGTH OF THE ATTENUATOR.
- 8. FLUORESCENT PRISMATIC LENS YELLOW SHEETING SHALL BE USED ON THE REFLECTIVE MARKERS. ALL REFLECTIVE SHEETING IS TO BE IN ACCORDANCE WITH SECTION 701 OF THE ROAD AND BRIDGE SPECIFICATIONS. STRIPES SHALL SLOPE DOWN TOWARD THE SIDE OF THE OBSTRUCTION ON WHICH TRAFFIC IS TO PASS.

COLOR:

FIELD - YELLOW (REFLECTORIZED)

MESSAGE - BLACK STRIPES (NON-REFLECTORIZED)

- 9. PAINT CHEVRON STRIPES AND INSTALL REFLECTIVE MARKERS ON PAVEMENT AT THE FRONT OF THE UNIT FOR MAXIMUM VISIBILITY.
- 10. MEASUREMENT AND PAYMENT:

TYPE 1 IMPACT ATTENUATOR WILL BE MEASURED IN UNITS OF EACH COMPLETE-IN-PLACE. PAYMENT SHALL BE FULL COMPENSATION FOR FURNISHING AND INSTALLING IMPACT ATTENUATOR, REFLECTORIZED MARKER, PORTLAND CONCRETE FOUNDATION, REQUIRED BACKUP, TRANSITION PANEL. AND ALL MATERIALS, LABOR, EXCAVATION, TOOLS, EQUIPMENT AND ANY INCIDENTALS NECESSARY TO COMPLETE THE WORK.

THROUGH ROADWAY MARKER POSITION LEFT OF TRAFFIC



THROUGH ROADWAY MARKER POSITION RIGHT OF TRAFFIC



MINIMUM 8' CLEAR AREA FOR ATTENUATOR REARWORD MOTION

STANDARD MB-7D. FINISHED GRADE STANDARD MB-7F, 2'-83/4" MIN. CONSTANT SLOPE BARRIER BRIDGE PARAPET TERMINAL WALLS

A REINFORCED CONCRETE FOUNDATION IS REQUIRED, -DESIGN DETAILS ARE TO BE FURNISHED BY THE IMPACT ATTENUATOR MANUFACTURER. MINIMUM COMPRESSIVE STRENGTH OF CONCRETE SHALL BE 4000 PSI.

**ELEVATION VIEW** 

ITEM CODE 13607 STD. IA-1 IMPACT ATTEN. (TL-3, >40 MPH DES.SP.) EACH

A COPY OF THE ORIGINAL SEALED AND SIGNED STANDARD DRAWING IS ON FILE IN THE CENTRAL OFFICE IMPACT ATTENUATOR **SPECIFICATION** REFERENCE 105 TYPE 1 RE-DIRECTIVE PERMANENT INSTALLATION (TL-3 > 40 MPH ) 221 REVISION DATE 505 VIRGINIA DEPARTMENT OF TRANSPORTATION MASH 2016 512

2016 ROAD & BRIDGE STANDARDS


 $\mathbb{V}$ DOT

ROAD AND BRIDGE STANDARDS

12/18

SHEET 1 OF 3 505.01

# 2016 ROAD & BRIDGE STANDARDS IA-1 TRAFFIC TRANSITION PANEL REQUIRED WITH TWO WAY TRAFFIC VARIABLE BASED ON MANUFACTURER VARIABLE BASED ON MANUFACTURER VARIABLE 4' MIN. SUB-BASE TO BE -PLAN VIEW COMPACTED UNDER CONC. FOUNDATION (BI-DIRECTIONAL) SECTION A-A X THE MINIMUM DISTANCE SHOWN IS A MINIMUM CLEAR SPACE REQUIRED FOR THE PROPER OPERATION OF THE IMPACT ATTENUATOR. STANDARD SHOULDER WIDTHS SHOULD BE DESIGNED AND MAINTAINED IN ACCORDANCE WITH CURRENT VDOT POLICY. SUB-BASE TO BE COMPACTED UNDER CONC. FOUNDATION TRAFFIC [ SECTION B-B -≫ B - VARIABLE BASED ON MANUFACTURER VARIABLE BASED ON MANUFACTURER VARIABLE 4' MIN. PLAN VIEW (UNI-DIRECTIONAL) a copy of the original sealed and signed standard drawing is on file in the central office IMPACT ATTENUATOR **\**VDOT **SPECIFICATION** REFERENCE ROAD AND BRIDGE STANDARDS 105 221 TYPE 1 RE-DIRECTIVE PERMANENT INSTALLATION (TL-3 > 40 MPH) SHEET 2 OF 3 REVISION DATE 505 12/18 MASH 2016 VIRGINIA DEPARTMENT OF TRANSPORTATION 505.02



STANDARD		
	THIS PAGE INTENTIONALLY LEFT BLANK	
	<b>T</b>	_
ROAD AND BRIDGE STANDARDS	TITLE	SPECIFICATION REFERENCE
SHEET 1 OF 1 REVISION DATE		
<u> </u>	VIRGINIA DEPARTMENT OF TRANSPORTATION	

NOTES IA-2

- DESIGN SHOWN IS REPRESENTATIONAL ONLY, SEE MANUFACTURER'S DRAWINGS FOR COMPONENTS AND INSTALLATION INSTRUCTIONS.
- 2. IMPACT ATTENUATOR SHALL BE SELECTED FROM VDOT'S PROVISIONALLY APPROVED MASH LIST, ALL UNITS MUST HAVE SUCCESSFULLY PASSED THE MASH 2016 TL-2 TESTING CRITERIA AND DEEMED REIMBURSABLE BY FHWA.
- 3. ALL STEEL HARDWARE COMPONENTS SHALL BE GALVANIZED.
- 4. IMPACT ATTENUATOR MANUFACTURER MUST FURNISH DETAILS FOR REQUIRED ANCHORING SYSTEM. FOR DIMENSIONS OF UNIT AND CONCRETE FOUNDATION SEE MANUFACTURER'S DRAWINGS AND SPECIFICATIONS.
- 5. CROSS SLOPE OF THE PAD SHALL NOT EXCEED A 8% (12:1) SLOPE.
- ANY LOCATION WHERE THERE IS REVERSE DIRECTION TRAFFIC, A TRANSITION PANEL SHALL BE SUPPLIED BY THE MANUFACTURER AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S DRAWINGS AND SPECIFICATIONS.
- 7. DUE TO THE VARYING LENGTHS OF PROPRIETARY IMPACT ATTENUATORS THE DESIGNER SHOULD ALLOW 15' FOR THE LENGTH OF THE ATTENUATOR.
- 8. FLUORESCENT PRISMATIC LENS YELLOW SHEETING SHALL BE USED ON THE REFLECTIVE MARKERS. ALL REFLECTIVE SHEETING IS TO BE IN ACCORDANCE WITH SECTION 701 OF THE ROAD AND BRIDGE SPECIFICATIONS. STRIPES SHALL SLOPE DOWN TOWARD THE SIDE OF THE OBSTRUCTION ON WHICH TRAFFIC IS TO PASS.

COLOR:

512

FIELD - YELLOW (REFLECTORIZED)

MESSAGE - BLACK STRIPES (NON-REFLECTORIZED)

- 9. PAINT CHEVRON STRIPES AND INSTALL REFLECTIVE MARKERS ON PAVEMENT AT THE FRONT OF THE UNIT FOR MAXIMUM VISIBILITY.
- 10. MEASUREMENT AND PAYMENT:

TYPE 1 IMPACT ATTENUATOR WILL BE MEASURED IN UNITS OF EACH COMPLETE-IN-PLACE. PAYMENT SHALL BE FULL COMPENSATION FOR FURNISHING AND INSTALLING IMPACT ATTENUATOR, REFLECTORIZED MARKER, PORTLAND CONCRETE FOUNDATION, REQUIRED BACKUP, TRANSITION PANEL. AND ALL MATERIALS, LABOR, EXCAVATION, TOOLS, EQUIPMENT AND ANY INCIDENTALS NECESSARY TO COMPLETE THE WORK.

11. SEE PAGE 505.03 FOR SITE PREPARATION REQUIREMENTS WHEN IMPACT ATTENUATOR IS INSTALLED ON A SHOULDER.

MINIMUM 8' CLEAR AREA FOR ATTENUATOR REARWORD MOTION

STANDARD MB-7D, FINISHED GRADE STANDARD MB-7F, 2'-8¾" MIN. CONSTANT SLOPE BARRIER, BRIDGE PARAPET TERMINAL WALLS

A REINFORCED CONCRETE FOUNDATION IS REQUIRED. -DESIGN DETAILS ARE TO BE FURNISHED BY THE IMPACT ATTENUATOR MANUFACTURER. MINIMUM COMPRESSIVE STRENGTH OF CONCRETE SHALL BE 4000 PSI.

#### ELEVATION VIEW

ITEM CODE 13606 STD. IA-2 IMPACT ATTEN. (TL-2, < 40 MPH DES.SP.) EACH

A COPY OF THE ORIGINAL SEALED AND SIGNED STANDARD DRAWING IS ON FILE IN THE CENTRAL OFFICE **SPECIFICATION** IMPACT ATTENUATOR REFERENCE 105 TYPE 1 RE-DIRECTIVE PERMANENT INSTALLATION (TL-2 < 40 MPH) 221 505 VIRGINIA DEPARTMENT OF TRANSPORTATION

MASH 2016

 $\mathbb{V}$ DOT ROAD AND BRIDGE STANDARDS REVISION DATE SHEET 1 OF 2

> 12/18 505.04

2016 ROAD & BRIDGE STANDARDS






THROUGH ROADWAY MARKER POSITION RIGHT OF TRAFFIC



GORE AREA REFLECTIVE MARKER



NOTES

- DESIGN SHOWN IS REPRESENTATIONAL ONLY, SEE MANUFACTURER'S DRAWINGS FOR COMPONENTS AND INSTALLATION INSTRUCTIONS.
- 2. IMPACT ATTENUATOR SHALL BE SELECTED FROM VDOT'S PROVISIONALLY APPROVED MASH LIST FOR TYPE I RE-DIRECTIVE LOW MAINTENANCE CATEGORY. ALL UNITS MUST HAVE SUCCESSFULLY PASSED MASH 2016 TL-3 TESTING CRITERIA AND BEEN ACCEPTED BY FHWA.
- ALL STEEL HARDWARE COMPONENTS SHALL BE GALVANIZED.
- 4. IMPACT ATTENUATOR MANUFACTURER MUST FURNISH DETAILS FOR REQUIRED ANCHORING SYSTEM. FOR DIMENSIONS OF UNIT AND CONCRETE FOUNDATION SEE MANUFACTURER'S DRAWINGS AND SPECIFICATIONS.
- 5. CROSS SLOPE OF THE PAD SHALL NOT EXCEED A 8% (12:1) SLOPE.
- ANY LOCATION WHERE THERE IS REVERSE DIRECTION TRAFFIC A TRANSITION PANEL SHALL BE SUPPLIED BY THE MANUFACTURER AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS DRAWINGS AND SPECIFICATIONS.
- DUE TO THE VARYING LENGTHS OF PROPRIETARY IMPACT ATTENUATORS THE DESIGNER SHOULD ALLOW 30' FOR THE LENGTH OF THE ATTENUATOR.
- FLUORESCENT PRISMATIC LENS YELLOW SHEETING SHALL BE USED ON THE REFLECTIVE MARKERS. ALL REFLECTIVE SHEETING IS TO BE IN ACCORDANCE WITH SECTION 701 OF THE ROAD AND BRIDGE SPECIFICATIONS. STRIPES SHALL SLOPE DOWN TOWARD THE SIDE OF THE OBSTRUCTION ON WHICH TRAFFIC IS TO PASS.

COLOR:

FIELD - YELLOW (REFLECTORIZED)

MESSAGE - BLACK STRIPES (NON-REFLECTORIZED)

- 9. PAINT CHEVRON STRIPES AND INSTALL REFLECTIVE MARKERS ON PAVEMENT AT THE FRONT OF THE UNIT FOR MAXIMUM VISIBILITY.
- 10. MEASUREMENT AND PAYMENT: LOW MAINTENANCE TYPE 1 IMPACT ATTENUATOR WILL BE MEASURED IN UNITS OF EACH COMPLETE-IN-PLACE. PAYMENT SHALL BE FULL COMPENSATION FOR FURNISHING AND INSTALLING IMPACT ATTENUATOR, REFLECTORIZED MARKER, PORTLAND CONCRETE FOUNDATION, REINFORCING STEEL, REQUIRED BACKUP, TRANSITION PANEL, AND ALL MATERIALS, LABOR, EXCAVATION, TOOLS, EQUIPMENT AND ANY INCIDENTALS NECESSARY TO COMPLETE THE WORK.
- 11. SEE PAGE 505.03 FOR SITE PREPARATION REQUIREMENTS WHEN IMPACT ATTENUATOR IS INSTALLED ON A SHOULDER.

STANDARD MB-7D. STANDARD MB-7F. FINISHED GRADE 2'-83/4" MIN. CONSTANT SLOPE BARRIER. BRIDGE PARAPET TERMINAL WALLS.

A REINFORCED CONCRETE FOUNDATION IS REQUIRED, — DESIGN DETAILS ARE TO BE FURNISHED BY THE IMPACT ATTENUATOR MANUFACTURER. MINIMUM COMPRESSIVE STRENGTH OF CONCRETE SHALL BE 4000 PSI.

ELEVATION VIEW

ITEM CODE 13603 IMPACT ATTEN. TY. 1 (TL-3, LOW MAINTENANCE) EACH

MINIMUM 8' CLEAR AREA FOR

ATTENUATOR REARWORD MOTION

A COPY OF THE ORIGINAL SEALED AND SIGNED STANDARD DRAWING IS ON FILE IN THE CENTRAL OFFICE **SPECIFICATION** IMPACT ATTENUATOR REFERENCE 105 LOW MAINTENANCE TYPE 1 RE- DIRECTIVE IMPACT ATTENUATOR 221 (TL-3 > 40 MPH)505 VIRGINIA DEPARTMENT OF TRANSPORTATION MASH 2016 512

THROUGH ROADWAY MARKER POSITION RIGHT OF TRAFFIC

IA-LM




THROUGH ROADWAY MARKER

POSITION LEFT OF TRAFFIC


GORE AREA REFLECTIVE MARKER


 $\mathbb{V}$ DOT ROAD AND BRIDGE STANDARDS REVISION DATE SHEET 1 OF 2


> 12/18 505.10




MGS-HDW









L= 11/4" FOR SPLICE BOLT-FULL LENGTH THREADS

L= 2" FOR SPLICE BOLT-FULL LENGTH THREADS ON NESTED W BEAMS.

L= 14" FOR STEEL POST WITH 12" BLOCKOUT BOLT-11/2" MIN. THREADS

L= 18" FOR STEEL POST WITH 16" BLOCKOUT DEPTH BOLT-2" MIN. THREADS

L= 26" FOR STEEL POST WITH 24" BLOCKOUT DEPTH BOLT-2" MIN. THREADS

# DETAIL OF BUTTON HEAD BOLT AND RECESS NUT (GUARDRAIL BOLT)

NOTES:

ALL HARDWARE IS TO BE GALVANIZED IN ACCORDANCE WITH THE SPECIFICATIONS.

SPECIFICATION REFERENCE

A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.

MGS STANDARD GUARDRAIL HARDWARE


221
505


VIRGINIA DEPARTMENT OF TRANSPORTATION

A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.

ROAD AND BRIDGE STANDARDS

REVISION DATE
NEW 02/17
506.01






STANDARD		
	THIS PAGE INTENTIONALLY LEFT BLANK	
	<b>T</b>	_
ROAD AND BRIDGE STANDARDS	TITLE	SPECIFICATION REFERENCE
SHEET 1 OF 1 REVISION DATE		
<u> </u>	VIRGINIA DEPARTMENT OF TRANSPORTATION	

GR-MGS1, 1A


TRAFFIC DIRECTION FOR RAIL LAP AS SHOWN

(SEE NOTE 7)



#### GR-MGS1

(6'-3" POST SPACING)
MIN. DISTANCE FROM FACE OF RAIL TO FIXED OBJECT = 60"




#### SPLICE DETAIL

RAIL SPLICE SHALL BE PLACED MID-SPAN FOR STANDARD POST SPACING (6'-3")

#### NOTES:

- GUARDRAIL LOCATIONS SHOWN ON PLANS ARE APPROXIMATE ONLY AND CAN BE ADJUSTED DURING CONSTRUCTION IF AND AS DIRECTED BY THE ENGINEER.
- 2. FOR DETAILS OF POST AND BLOCKOUTS SEE SHEET NO. 506.05.
- 3. FOR DETAILS OF RAIL ELEMENT, AND ASSOCIATED HARDWARE SEE SHEETS 506.01 AND 506.02.
- 4. RAIL ELEMENTS WITH RADII LESS THAN OR EQUAL TO 150 FEET SHALL BE SHOP CURVED AND PAID FOR AS RADIAL GR-MGS1, OR 1A.
- ALL GR-MGS1 AND GR-MGS1A RAIL SHALL BE MAINTAINED AT A HEIGHT OF 30" MIN - 32" MAX AS MEASURED PER STANDARD GR-INS.
- 6. ALL GUARDRAIL POSTS SHALL BE SET PLUMB. POST SHALL NOT BE SET WITH A VARIATION OF MORE THAN 1/8" PER FOOT FROM VERTICAL. W-BEAM, BLOCKOUTS, AND POSTS SHALL BE SET AND ALIGNED WITHOUT ALTERATION OR FORCE, AS PER SECTION 505 OF THE SPECIFICATIONS.



#### GR-MGS1A

(3'-1)/2'' POST SPACING) MIN. DISTANCE FROM FACE OF RAIL TO FIXED OBJECT = 48"

FLARE RATES			
ND INE			
RE E			
<b>k</b>			
<b>k</b>			
ŧ			
<b>k</b>			
ŧ			
* *			

- \* SUGGESTED MAXIMUM FLARE RATE FOR SEMI-RIGID BARRIER SYSTEMS.
- ALL W-BEAM RAILS SHALL BE LAPPED IN THE DIRECTION OF VEHICULAR TRAVEL FOR THE FINISHED ROADWAY.
- ADJUSTING EXISTING GUARDRAIL TO MEET THE MGS1 STANDARD IS NOT PERMITTED.

DESCRIPTIO	N		ITEM CO	DE
GUARDRAIL	GR-MGS	51	13280	LF
GUARDRAIL	GR-MGS	S1A	13281	LF
GUARDRAIL	GR-MGS	S1, 9' POST	13282	LF
GUARDRAIL	RADIAL	GR-MGS1	13283	LF
GUARDRAIL	RADIAL	GR-MGS1A	13284	LF
GUARDRAIL	RADIAL	GR-MGS1, 9' POST	13285	LF

SPECIFICATION REFERENCE

A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.

MIDWEST GUARDRAIL SYSTEM

(STANDARD AND REDUCED POST SPACING)


VIRGINIA DEPARTMENT OF TRANSPORTATION


REVISION DATE
SHEET 1 OF 2

VIRGINIA DEPARTMENT OF TRANSPORTATION

NEW 02/17

506.04





- TANGENT END TERMINAL (GR-MGS2) SHALL BE A VDOT APPROVED PRODUCT MEETING MASH TESTING CRITERIA, ANY TERMINAL USED FOR THE GR-MGS2 SHALL BE FROM THE VDOT APPROVED PRODUCTS LIST.
- ALL TERMINALS SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S INSTALLATION INSTRUCTIONS AND THE FOLLOWING VDOT REQUIREMENTS:
  - ALL STANDARD GR-MGS2 TERMINALS (SIMILAR TO AS SHOWN ABOVE) SHALL BE INSTALLED WITHOUT AN OFFSET.
  - B. INSTALLING GR-MGS2 TERMINAL ON A RADIUS IS NOT PERMITTED.
  - DIRECTION OF THE REFLECTIVE TAPE ON THE TERMINAL HEAD SHALL CONFORM TO MUTCD APPLICATION FOR DIAGONAL STRIPES ON OBJECT MARKERS AND BRIDGE END PANELS. (SEE NOTE 4)
  - D. DO NOT CHANGE THE LAPPING OF TERMINAL FOR ANY INSTALLATIONS. INSTALL AS SHOWN IN THE MANUFACTURER'S INSTALLATION INSTRUCTIONS REGARDLESS OF ADJACENT TRAFFIC DIRECTION. (SEE DETAIL THIS SHEET)
  - E. HEIGHT MEASURED AT TOP OF W-BEAM IS 30" MIN. 32" MAX.
- THIS DRAWING IS REPRESENTATIONAL ONLY. DETAILS, DIMENSIONS, QUANTITIES, AND OTHER INFORMATION NOT SHOWN WILL VARY FOR EACH MANUFACTURER. SEE INDIVIDUAL MANUFACTURER'S PLANS FOR THIS INFORMATION.

4. FLUORESCENT PRISMATIC LENS YELLOW SHEETING SHALL BE USED ON THE REFLECTIVE MARKERS. ALL REFLECTIVE SHEETING IS TO BE IN ACCORDANCE WITH SECTION 701 OF THE ROAD AND BRIDGE SPECIFICATIONS. STRIPES SHALL SLOPE DOWN TOWARD THE SIDE OF THE OBSTRUCTION ON WHICH TRAFFIC IS TO PASS.

FIELD - YELLOW (REFLECTORIZED) MESSAGE - BLACK STRIPES (NON-REFLECTORIZED)




THROUGH ROADWAY MARKER POSITION LEFT OF TRAFFIC




THROUGH ROADWAY MARKER POSITION RIGHT OF TRAFFIC


		ITEM CO	DE 13286 EACH
SPECIFICATION REFERENCE	a copy of the original sealed and signed drawing is on file in the central office.  MIDWEST GUARDRAIL SYSTEM	V	
	MIDWEST GUARDRAIL SYSTEM	ROAD AND BRID	GE STANDARDS
221 236 505	(TANGENT END TERMINAL)	REVISION DATE	SHEET 1 OF 3
505	VIRGINIA DEPARTMENT OF TRANSPORTATION	09/17	506.06





GR-MGS2




STANDARD		
	THIS PAGE INTENTIONALLY LEFT BLANK	
	<b>T</b>	_
ROAD AND BRIDGE STANDARDS	TITLE	SPECIFICATION REFERENCE
SHEET 1 OF 1 REVISION DATE		
<u> </u>	VIRGINIA DEPARTMENT OF TRANSPORTATION	








STANDARD		
	THIS PAGE INTENTIONALLY LEFT BLANK	
	<b>T</b>	_
ROAD AND BRIDGE STANDARDS	TITLE	SPECIFICATION REFERENCE
SHEET 1 OF 1 REVISION DATE		
<u></u>	VIRGINIA DEPARTMENT OF TRANSPORTATION	




# MEASURING GUARDRAIL HEIGHT ON FRONT SLOPE RELATIVE TO SHOULDER HINGE POINT



MEASURING GUARDRAIL HEIGHT & RAIL OFFSET FROM FACE OF CURB OR CURB & GUTTER APPLICABLE FOR DESIGN SPEEDS OF 45 MPH AND LESS.

THE OPTION TO OFFSET GUARDRAIL FROM THE FACE OF CURB IS APPLICAPLE FOR DESIGN SPEEDS OF 45 MPH AND LESS.



SPECIFICATION REFERENCE MGS

505


A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.


MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA

VIRGINIA DEPARTMENT OF TRANSPORTATION

ROAD AND BRIDGE STANDARDS

REVISION DATE SHEET 1 OF 4
NEW 02/17 507.01







NOTE:
PAVED SHOULDER WIDTHS SHOWN ARE MINIMUM.
THE PAVED SHOULDER MAY BE EXTENDED TO THE
FACE OF THE RAIL. THE PAVED WIDTH USED SHALL
BE IN ACCORDANCE WITH THE ROADWAY
CLASSIFICATION AS DEFINED IN THE ROAD DESIGN
MANIJAL

SEE STANDARD MC-4 FOR PAVING UNDER GUARDRAIL.

#### TABLE I

NORMAL GUARDRAIL LOCATION-THROUGH TRAFFIC LANES LEFT OF TRAFFIC

	MITIC LANES LLI I	OI IIVALLIC
TOTAL SHOULDER WIDTH (S) (PAVED & GRADED)	WIDTH (PS)	OFFSET FROM EDGE OF TRAVELED WAY TO FACE OF GUARDRAIL (O)
18'	12'	14'
16'	4' or 10'	12'
14'	4' or 8'	10'
12'	3', 4', 5', or 6'	8'
10'	3' or 4'	6'
9'	3' or 4'	5'
8'	0 or 2'	4'
6'	0	2'

#### TABLE II

NORMAL GUARDRAIL LOCATION-THROUGH

TRAFFIC LANES RIGHT OF TRAFFIC			
TOTAL SHOULDER WIDTH (S) (PAVED & GRADED)	PAVED SHOULDER WIDTH (PS) (SEE NOTE)	OFFSET FROM EDGE OF TRAVELED WAY TO FACE OF GUARDRAIL (O)	
18'	12'	14'	
16'	6' or 10'	12'	
14'	8'	10'	
12'	4', 5', or 6'	8'	
10'	0 or 4'	6'	
9'	0 or 4'	5'	
8'	0 or 2'	4'	
6'	0	2'	

NORMAL GUARDRAIL LOCATION

ROAD AND BRIDGE STANDARDS

SHEET 2 OF 4 REVISION DATE

507.02 REW 02/17

A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.

MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA

VIRGINIA DEPARTMENT OF TRANSPORTATION

SPECIFICATION REFERENCE 221 505

REVISION DATE


09/17

SHEET 3 OF 4


507.03

221


505



GR-MGS-INS




### MOW STRIP/PAVEMENT PLAN



POST AND BLOCKOUT 14" MIN. \* PLACE POST ON CENTERLINE OF **OPENING** W-BEAM GUARDRAIL 24" MINIMUM ROUND OPENING

#### ROCK INSTALLATION PLAN VIEW



ROCK INSTALLATION ELEVATION

#### NOTES:

- LEAVE-OUT ALLOWS FOR PROPER POST ROTATION.
- 2. DO NOT SHORTEN POST. POST SHALL HAVE FULL EMBEDMENT.

MOW STRIP/PAVEMENT ELEVATION

INSTALL POST AFTER OPENING IS BACKFILLED AND COMPACTED IN 6" LIFTS.

**SPECIFICATION** A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE. REFERENCE MGS W-BEAM GUARDRAIL INSTALLATION CRITERIA 221 (LEAVE-OUT FOR STANDARD GUARDRAIL POST INSTALLATION) 505


VIRGINIA DEPARTMENT OF TRANSPORTATION


 $\mathbb{V}$ DOT ROAD AND BRIDGE STANDARDS

REVISION DATE NEW 04/19

SHEET 5 OF 5 507.05

STANDARD		
	THIS PAGE INTENTIONALLY LEFT BLANK	
	<b>T</b>	_
ROAD AND BRIDGE STANDARDS	TITLE	SPECIFICATION REFERENCE
SHEET 1 OF 1 REVISION DATE		
<u></u>	VIRGINIA DEPARTMENT OF TRANSPORTATION	






#### 2016 ROAD & BRIDGE STANDARDS TCB-1 3" STANDARD FOUNDRY LETTERS RECESSED 1/4 INTO TOP CONCRETE SURFACE. (SEE NOTE 3) | MASH 2016 00-0000 MASH 2016 00-0000 YEAR MONTH: 12'-6 PLAN VIEW - 21/4''--RV0401 SPACING MEASURED TO THE CENTER OF THE BAR 91/2" 8¾" 81/2" 81/2" 17" 81/2" 5" $25\frac{1}{2}$ 81/21 81/2" 83/4' 6" -MI 01 22" -ML02 17' 32' 17" -ML01 6 5" 3'' A 3'-3' 3'-3' 81/2" 81/2" LIFT SLOT LIFT SLOT 24" **ELEVATION VIEW** NOTES: END VIEW 1" CHAMFER THE TEMPORARY CONCRETE BARRIER SHALL BE PRECAST BY A VDOT APPROVED PRECAST MANUFACTURER. THE MANUFACTURER SHALL SUBMIT SHOP DRAWINGS FOR APPROVAL BY THE STANDARDS & SPECIAL DESIGN SECTION. MODIFICATIONS TO THIS DESIGN ARE NOT PERMITTED. ¾" CHAMFER 8" X 12" BARRIER ÍŸP. VERTICAL PANELS BARRIER SHALL HAVE A UNIFORM NATURAL CONCRETE FINISH. THE BARRIER SHALL AS REQUIRED. NOT BE PAINTED OR COATED OTHER THAN MARKINGS NECESSARY TO IDENTIFY THE - 21/2" LIFT SLOT (SEE NOTE 14) MANUFACTURER. THE RECESSED LETTERING IN THE TOP OF THE BARRIER CONTAINING MASH 2016 ALONG WITH CHAMFER MLO: MONTH AND YEAR OF MANUFACTURE IS REQUIRED FOR EACH BARRIER SEGMENT PRODUCED. BARRIER DELINEATOR CONCRETE SHALL BE A MINIMUM OF 5000 PSI. 6'' (SEE NOTES 11, 12, & 13) ALL REINFORCING STEEL SHALL BE IN ACCORDANCE WITH ASTM-A615 GRADE 60. ML<sub>02</sub> ALL REINFORCING STEEL SHALL HAVE A MINIMUM COVER OF 2" UNLESS OTHERWISE SHOWN. 6. 6" RV0401 LOOP BARS SHALL NOT BE USED TO LIFT, MOVE, OR REPOSITION THE BARRIER. 6'' ONLY ONE TYPE OF TEMPORARY BARRIER IS PERMITTED IN A RUN. MIXING TEMPORARY ML01 CONCRETE BARRIER WITH OTHER TEMPORARY CONCRETE BARRIERS IS NOT PERMITTED. 5" OTHER PRECAST TEMPORARY CONCRETE BARRIERS SHALL BE FROM THE MASH PROVISIONALLY APPROVED LIST. BARRIERS THAT HAVE BEEN APPROVED BY VDOT ON THE MASH PROVISIONALLY 61/2" APPROVED LIST MAY BE SUBSTITUTED FOR THIS STANDARD 10. MAXIMUM CROSS SLOPE FOR PLACEMENT OF TEMPORARY BARRIER WILL BE 10:1. BARRIER DELINEATOR SIZE, COLOR AND SPACING SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS. SECTION A-A BARRIER DELINEATOR REFLECTIVE SURFACE IN ALL INSTANCES SHALL BE FACING ONCOMING TRAFFIC. LONGITUDNAL REINFORCEMENT SPACING MEASURED TO THE CENTER OF THE BAR COST OF DELINEATOR SHALL BE INCLUDED IN THE PRICE BID FOR TEMPORARY CONCRETE BARRIER. BARRIER VERTICAL PANELS SHALL BE SPACED IN ACCORDANCE WITH VIRGINIA WORK AREA PROTECTION MANUAL. **SPECIFICATION** $\mathbb{V}$ DOT A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE. REFERENCE TEMPORARY CONCRETE BARRIER ROAD AND BRIDGE STANDARDS 105 (MASH FREESTANDING PRECAST PIN AND LOOP FOR TEMPORARY USE) REVISION DATE SHEET 1 OF 3


VIRGINIA DEPARTMENT OF TRANSPORTATION

NEW 04/20

509.01

512





SUGGESTED MAXIMUM FLARED RATE FOR RIGID BARRIER SYSTEMS.

REVISION DATE

NEW 04/20


 $\mathbf{V}$ DOT

ROAD AND BRIDGE STANDARDS

SHEET 2 OF 3

502.05

WHEN USING VDOT STANDARD TCB-1 WITH THE PIN AND LOOP POSITIVE CONNECTION, ALLOW FOR A 6'-8" DYNAMIC DEFLECTION. PROVIDE MIN. 60' OF BARRIER UPSTREAM AND DOWNSTREAM OF WORK ZONE FOR ANCHORAGE FOR APPROVED NON-VDOT DESIGNS, REFER TO MANUFACTURER'S INSTALLATION INSTRUCTIONS FOR DEFLECTIONS AND ANCHORAGE



**SPECIFICATION** 

REFERENCE


105

512

A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE.

TEMPORARY CONCRETE BARRIER

(MASH FREESTANDING PRECAST PIN AND LOOP FOR TEMPORARY USE) VIRGINIA DEPARTMENT OF TRANSPORTATION



STANDARD		
	THE DAOE INTENTIONALLY LEFT DI ANII	
	THIS PAGE INTENTIONALLY LEFT BLANK	
VDOT		SPECIFICATION REFERENCE
ROAD AND BRIDGE STANDARDS	TITLE	REFERENCE
SHEET 1 OF 1 REVISION DATE	VIRGINIA DEPARTMENT OF TRANSPORTATION	